

# CITY OF AUSTIN, TEXAS AUSTIN RESOURCE RECOVERY

### SHEETS:

A-0-00 COVER
A-1-01 SITE PLAN
A-1-10 DEMOLITION PLAN
A-1-11 PROPOSED CONDITIONS PLAN
E-0-00 ELECTRICAL GENERAL NOTES
E-1-01 ELECTRICAL DEMOLITION - LEVEL
E-1-02 ELECTRICAL NEW - LEVEL 1
E-6-01 ELECTRICAL SCHEDULE
M-0-00 MECHANICAL GENERAL NOTES
M-1-01 MECHANICAL PLAN
M-4-01 MECHANICAL DETAILS
E-0-00 ELECTRICAL GENERAL NOTES
P-0-00 PLUMBING GENERAL NOTES


P-5-01 PLUMBING DETAILS
S-1 GENERAL NOTES
S-2 SPECIAL INSPECTION AND ABBREVIATION

S-3 NEW TRENCH DRAIN SUMP PIT PLAN IN EXISTING FOUNDATION
S-4 CONCRETE DETAILS

# NOTES:

- THIS PROJECT IS LOCATED WITHIN THE WILLIAMSON CREEK WATERSHED (CLASSIFIED AS (SUBURBAN) ) AND SHALL BE DEVELOPED, CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH CHAPTER 25 OF THE CODE OF THE CITY OF AUSTIN.
- 2. NO PORTION OF THIS SITE IS LOCATED WITHIN PARKLAND OR LAND USED FOR PARK PURPOSES.
- 3. NO PORTION OF THIS SITE IS LOCATED WITHIN THE 100-YEAR FLOODPLAIN, PER CITY OF AUSTIN AND FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP(S) NO 48453C0605k, DATED 0122/2020.
- 4. THIS PROJECT IS NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS DEFINED BY THE CITY OF AUSTIN. THIS PROJECT IS NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS REGULATED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ).
- 5. THERE ARE NO CRITICAL ENVIRONMENTAL FEATURES WITHIN 150' OF ANY PORTION OF THIS PROJECT. A FIELD INVESTIGATION HAS NOT BEEN PERFORMED AS A PART OF THIS PROJECT.

# KGSC TRUCK WASH FACILITY RETROFIT SUB PROJECT ID: 5773.025



### PROJECT INFORMATION

STREET ADDRESS: 4108 TODD LANE AUSTIN, TEXAS 78744


OWNER: AUSTIN RESOURCE RECOVERY

SUBMITTAL PREPARED BY:
CONTACT:
MWM DESIGNGROUP, INC.
305 E. HUNTLAND DR. STE. 200
(512) 453-0767 FAX: (512) 453-1734

OWEN HARROD, AIA, LEED AP BD+C (512) 992-2971
OwenH@mwmdesigngroup.com








1"	
<b>≟</b>	KGSC TRUCK WASH FACI
re	PROPOSED IMPROVEME
nch	


WASH FACILITY
MPROVEMENTS

PLOTTED: 11/25/2020

JOB NO: 023-92B

4108 TODD LANE AUSTIN, TEXAS 78744 A-0-00










drawing. Adjust scales accordingly.

4108 TODD LANE AUSTIN, TEXAS 78744

A-1-10



#### **ELECTRICAL ABBREVIATIONS**

ELECTRICAL ABBREVIATIONS			
AMPERE	A(AMP)	GALVANIZED GENERAL CONTRACTOR	GALV. GC
ABOVE	A(AIVIP) ABV	GROUND	_GC GND,G
ABOVE FINISHED FLOOR	AFF	GROUNDING ELEC. CONDCTOR	GEC
ABOVE FINISHED TEOOR	AFG	GROUND FAULT CIRCUIT	GEC GFCI,GF
AIR CONDITIONING	AIG A/C	INTERRUPTER	
ALUMINUM	A/C AL	INTERROT TER	
APPROXIMATE(LY)	APPROX.	HEATING, VENTILATION & AIR	HVAC
ARCHITECT(URAL)	ARCH('L).	CONDITIONING	
AUTHORITY HAVING	ARCH( L).  AHJ	661151116111116	
JURISDICTION	АПЈ	INFORMATION	INFO
JORISDICTION		INTERIOR	INT.
BELOW	BLW	ISOLATED GROUND	_iG
BREAKER	BKR		
BUILDING	BLDG.	JUNCTION BOX	JB,(J-BOX
DOILDING			
CARD READER	CR	KILOAMPERE INTERRUPTING	kAIC
CEILING	CLG	CAPACITY	<del></del>
CIRCUIT	CKT	KILOVOLT-AMPS	kVA
CONCRETE MASONRY UNIT	CMU	-	_
CONDENSATE DRAIN	COND.	LIGHTING CONTACTOR	LC
COPPER	CU	LIGHTING CONTROL PANEL	LCP
CONDUIT	С.		_
COUNTER	CTR	MAIN CIRCUIT BREAKER	MCB
CURRENT TRANSFORMER	СТ	MAIN LUG ONLY	MLO
		MANUFACTURE(R)	MFR.
DEMOLISH(ITION)	DEMO.	MAXIMUM	MAX
DEPARTMENT /	DEPT.	MAXIMUM OVERCURRENT	MOCP
DETAIL	DET.	PROTECTION	_
DISCONNECT	DISC.	MECHANICAL	MECH.
DIVISION	DIV.	MINIMUM	MIN.
DRAWING(S)	DWG(S)	MINIMUM CURRENT AMPACITY	
· · · · · · · · · · · · · · · · · · ·		MISCELLANEOUS	MISC.
EACH	EA.	MOUNTING HEIGHT TO CENTER	+(#)"
ELECTRICAL CONTRACTOR	EC	LINE OF DEVICE AFF OR AFG	
ELECTRIC(AL)	ELEC.		
ELECTRIC WATER COOLER	EWC	NATIONAL ELECTRICAL CODE	_NEC
ELEVATOR	ELEV.	NEMA 1, NEMA 3R, NEMA	N1,N3R,N
EMERGENCY	EM,EMER	RATING (AS NOTED)	
ENGINEER	ENGR.	NIGHT LIGHT	_NL
EQUIPMENT	EQPT.	NOMINAL	NOM.
ETCETERA	ETC.	NOT APPLICABLE	_N/A
EXHAUST FAN	EF	NOT IN CONTRACT	N.I.C.
EXISTING	EXIST.,(E)	NOT TO SCALE	N.T.S.
EXISTING RELOCATED	ER	NUMBER	_NO. <i>,</i> #
EXISTING TO REMAIN	ETR		
		PANEL	_PNL
FIRE ALARM	F/A	PARTIAL	_PART.
FIRE ALARM CONTROL PANEL	FACP	PHASE	PH.,Ø
FIRE ALARM ANNUNCIATOR	FAAP	PHOTOCELL	_PC
PANEL		POLE	P
FIRE / SMOKE DAMPER	F/S	POLYVINYL CHLORIDE	PVC
FOOT/FEET	FT.	POWER POLE	PP_

NOTE: NOT ALL ABBREVIATIONS ON THIS LIST ARE APPLICABLE TO THIS PROJECT.	

DEFED TO / DEFEDENCE	RECEPT.
	REF.
REQUIRE(D)	 REQ.('D)
RIGID GALVANIZED STEEL	RGS
ROOM	 RM
	_
SERVICE DISTRIBUTION	SDE
ENCLOSURE	_
SPECIFICATION(S)	SPEC.(S)
SQUARE	SQ.
SQUARE FEET	SF
STRUCTURED MEDIA CENTER	SMC
SURGE PROTECTIVE DEVICE	 SPD
SWITCH	SW.
TELEPHONE / DATA COMBO	TELEDATA
TELEPHONE	TEL.
TELEPHONE MOUNTING BOARD	TMB
TELEVISION	TV
TEXAS	TX
THROUGH	 THRU
TIMECLOCK	TC
TRANSFORMER	XFMR
TYPICAL	TYP
	_
UNDERGROUND	UG
UNDERWRITER LABORATORIES	UL
INC.	<del></del>
UNINTERRUPTIBLE POWER	UPS
SUPPLY	
UNLESS NOTED OTHERWISE	UNO
UTILITY	UTIL.
VOLT-AMPS	VA
VOLTAGE / VOLTS	V
WEATHER PROOF	WP
MALATITED DECICEANT	WR
WEATHER RESISTANT	/
WITH	W/

RECEPT.

QUANTITY

**RECEPTACLE** 

APPLICABLE CODES
2012 IBC
2020 NEC
2015 IECC
2012 TAS
2015 IFC
LOCAL CODES AND ORDINANCES

VOLTAGE DROP TABLE (20A CIRCUITS ONLY)							
	208V, 1Ø 120V, 1Ø						
#12 AWG	0 - 90 FT.	0 - 50 FT.					
#10 AWG	91 - 150 FT.	51 - 90 FT.					
#8 AWG	151 - 250 FT.	91 - 140 FT.					
#6 AWG	251 - 390 FT.	141 - 225 FT.					
#4 AWG	391 - 630 FT.	226 - 300 FT.					
(VERIFY MI	NIMUM VOLTAGE DR SIZE, PER N.E.C	_					

CVMADO	DECEDITION	CV/N 4D C !	DECONDENS
SYMBOL A	DESCRIPTION  1X4 LINEAR FIXTURE W/ DESIGNATION	SYMBOL	DESCRIPTION  PANELBOARD OR LOAD CENTER - SURFACE MOUN
	·		RECESSED MOUNT
LIA .	2X2 LINEAR FIXTURE W/ DESIGNATION		TRANSFORMER
A	2X4 LINEAR FIXTURE W/ DESIGNATION	<u>Б</u>	DISCONNECT SWITCHES - NON-FUSED, FUSED. FU SIZES NOTED ON DRAWINGS WITH "AF".
	EMERGENCY LIGHT FIXTURE (HALF-SHADED FOR ANY FIXTURE)	$\boxtimes$	MAGNETIC MOTOR STARTER
A	LINEAR 6" OR SLOT FIXTURE W/ DESIGNATION	<u>_</u> ⊠	COMBINATION STARTER AND DISCONNECT
⊢O-Ä	LINEAR STRIP FIXTURE W/ DESIGNATION		VARIABLE FREQUENCY DRIVE (VFD), COMBINATIO VFD AND DISCONNECT
	RECESSED DOWNLIGHT FIXTURE W/ DESIGNATION	Ó	MOTOR
O <sup>A</sup>	SURFACE DOWNLIGHT FIXTURE W/ DESIGNATION	<u> </u>	PUSHBUTTON - SINGLE, MUSHROOM HEAD
	PENDANT FIXTURE W/ DESIGNATION	<u> </u>	METER - PLAN VIEW, ONE-LINE DIAGRAM
	WALL WASH FIXTURE W/ DESIGNATION, DIRECTION		METER BANK
	INDICATED BY TRIANGLE  WALL MOUNT LINEAR FLUORESCENT FIXTURE W/		
A	DESIGNATION	<del></del>	UNISTRUT RACK
Q <sup>A</sup>	WALL MOUNT FIXTURE W/ DESIGNATION		LIGHTING CONTROLS
$\sum$	SPOTLIGHT	(v)	OCCUPANCY SENSOR, VACANCY SENSOR - CEILING MOUNTED
<u> </u>	CEILING W/ FACE INDICATED; WALL W/ FACE, EMERGENCY HEADS, AND DIRECTIONAL ARROWS (INSTALL FACES AND ARROWS AS INDICATED)	Ø+ Ø+	OCCUPANCY SENSOR, VACANCY SENSOR - MOUNT HIGH ON WALL
₩	EMERGENCY BATTERY FIXTURE	PC	PHOTOELECTRIC CELL
 *	CEILING FAN	LC	LIGHTING CONTACTOR
<b>→</b>	POLE LIGHT (ARM MOUNT, POST-TOP MOUNT)	TC	TIMECLOCK
•	BOLLARD FIXTURE	LCP	LIGHTING CONTROL PANEL
Ф	SINGLE 20A RECEPTACLE AT 18" UNLESS NOTED	02	DAYLIGHT ZONE SENSOR
Ф	20A DUPLEX RECEPTACLE AT 18" UNLESS NOTED	\$	LIGHT SWITCH AT 48" UNLESS NOTED
<b>₩</b>	20A GFI DUPLEX RECEPTACLE AT 18" UNLESS NOTED	D	DIMMER SWITCH AT 48" UNLESS NOTED
#	DOUBLE 20A DUPLEX RECEPTACLE AT 18" UNLESS NOTED	<b>S</b>	LOW-VOLTAGE SMART LIGHT SWITCH AT 48" UNLI
ф	20A DUPLEX RECEPTACLE 6" ABOVE COUNTER UNLESS		SUBSCRIPTS
	NOTED  20A DUPLEX RECEPTACLE SPECIAL MOUNT (FLOOR,	_	
• •	CEILING)	3	3-WAY SWITCH
<b>⊎</b> IG	20A ISOLATED GROUND RECEPTACLE	4	4-WAY SWITCH
<b>⊌</b> WP	20A RECEPTACLE WITH WEATHERPROOF "EXTRA DUTY" COVER AND WEATHER-RESISTANT GFCI RECEPTACLE	F	SINGLE POLE CEILING FAN & LIGHT SWITCH WITH 3-SPEED FAN CONTROL TO ALLOW CONTROL OF FAINDEPENDENT OF LIGHT KIT
<b>₩</b> €	COMBINATION DUAL USB WITH DUPLEX RECEPTACLE	К	KEY-OPERATED SWITCH
<b>4</b> 30	SPECIAL RECEPTACLE (RATING NOTED)	М	MOTOR-RATED SWITCH
▼ ‡	COMBINATION TELEPHONE/DATA (TELE-DATA) OUTLET (18" ON WALL, 6" ABOVE COUNTER)	0	OCCUPANCY SENSOR SWITCH
$\overline{\mathbf{V}}$	COMBINATION TELEPHONE/DATA (TELE-DATA) OUTLET SPECIAL MOUNT (FLOOR, CLG)	Р	SWITCH WITH PILOT LIGHT
▼ ▽	TELEPHONE OUTLET, DATA OUTLET	R	RED EMERGENCY BRANCH SWITCH
ф	TELEVISION CABLE CONNECTION AT 58" A.F.F. UNLESS OTHERWISE NOTED.	Т	TIMER SWITCH
∇ <sup>FOB</sup>	LOW-VOLTAGE OR DATA OUTLET INTENDED FOR SPECIFIC PURPOSE (CARD READER, FOB SECURITY DEVICE SHOWN)	V	VACANCY SENSOR SWITCH (AUTO OFF, MANUAL C
(J) (D)	J-BOX (CEILING/WALL, FLOOR)	a	LOWER CASE LETTER AT FIXTURES AND SWITCHES ETC.) INDICATES SWITCHING CONTROL.
	SECURITY CAMERA		FIRE ALARM SYSTEM
S SH	SPEAKER - CEILING MOUNTED, WALL MOUNTED	FACP	FIRE ALARM CONTROL PANEL
	WIFI OUTLET - CEILING MOUNTED CONDUIT RUN EXPOSED OR CONCEALED	FAAP F	FIRE ALARM ANNUNCIATOR PANEL  MANUAL PULL STATION DOUBLE ACTION
	CONDUIT RUN BELOW FLOOR OR GRADE		GENERAL ALARM COMBINATION HORN/STROBE
	ITEM TO BE REMOVED		(AUDIO/VISUAL) (WALL, CLG)  FIRE ALARM STROBE (VISUAL DEVICE) (WALL, CLG)
	SWITCHLEG		SMOKE/IONIZATION DETECTOR
	CIRCUIT HOMERUN, #12, THWN/THHN & QTY AS REQ'D, W/ GND, 3/4"C., UNLESS NOTED	<b>(</b>	HEAT DETECTOR
<del>\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\</del>	CIRCUIT HOMERUN CONTAINING 3 HOTS, NEUTRAL,	<b>?</b> -	DUCT DETECTOR
	GROUND, AND ISOLATED GROUND  CONDUIT STUB-UP - CAP & MARK	<b>©</b>	COMBINATION SMOKE / CARBON MONOXIDE DETECTOR
→	CONDUIT OR CIRCUIT BREAK/CONTINUATION (DIAGRAMMATIC ONLY)	B	BEAM DETECTOR
——————————————————————————————————————	GROUND	FS	SPRINKLER SYSTEM FLOW SWITCH
r ·		TS	SPRINKLER SYSTEM TAMPER SWITCH
			ELECTRIC DOOR HOLDER

#### **ELECTRICAL GENERAL NOTES**

- 1. THESE DRAWING NOTES ACCOMPANY THE PUBLISHED CONSTRUCTION DOCUMENT SPECIFICATION BOOK (PROJECT MANUAL).
- 2. EXISTENCE AND LOCATION OF DEVICES, FIXTURES, EQUIPMENT, CIRCUITING, ETC. THAT ARE SHOWN TO BE EXISTING WAS TAKEN FROM EXISTING DRAWINGS AND/OR VISUAL INSPECTION AND SHOULD BE VERIFIED IN FIELD PRIOR TO ANY PRICING OR WORK.
- 3. ELECTRICAL CONTRACTOR SHALL VISIT SITE AND SHALL BECOME FAMILIAR WITH SITE CONDITIONS AND VERIFY DIMENSIONS AND WORK TO BE INSTALLED PRIOR TO SUBMITTING A BID: BY SUBMITTING A BID, CONTRACTOR CERTIFIES FAMILIARITY WITH EXISTING JOBSITE CONDITIONS PRIOR TO COMMENCEMENT OF WORK; FAILURE TO DO SO WILL NOT BE CAUSE FOR EXTRA WORK COMPENSATION.
- 4. ALL MATERIAL SHALL BE NEW AND SHALL BE LISTED OR LABELED BY U.L. OR OTHER RECOGNIZED TESTING FACILITY.
- 5. WIRE TERMINATION PROVISIONS FOR PANELBOARDS, CIRCUIT BREAKERS, SAFETY SWITCHES, AND ALL OTHER ELECTRICAL APPARATUS SHALL BE LISTED AS SUITABLE FOR AT LEAST 75°C. (CU/AL) OR AS NOTED IN MANUFACTURER'S INSTRUCTIONS, WHICHEVER IS GREATER.
- 6. FURNISH ALL MATERIAL, LABOR, EQUIPMENT AND PERMITS TO PROVIDE A COMPLETE, OPERATIONAL ELECTRICAL SYSTEM CONSISTENT WITH THE INTENT OF THE DRAWINGS. WHERE THE WORD "PROVIDE" IS USED, IT SHALL MEAN, "FURNISH AND INSTALL COMPLETE AND READY FOR USE".
- INSTALLATIONS FOUND NOT COMPLYING WITH SPECIFIED WORKMANSHIP PRACTICES SHALL BE REVISED TO COMPLY AT NO ADDITIONAL COST TO THE OWNER.
- 8. ELECTRICAL CONTRACTOR SHALL PERFORM WORK IN A SAFE MANNER AND MAINTAIN ADEQUATE PROTECTION OF WORK, THE OWNER'S PROPERTY AND ALL PERSONS ON SITE FROM INJURY, DAMAGE OR LOSS
- PIELD-COORDINATE LOCATION OF PANELS, CONDUITS AND DEVICES WITH STRUCTURAL MEMBERS AND EQUIPMENT FROM OTHER TRADES. CAREFULLY COORDINATE INSTALLATION SCHEDULES WITH OTHER TRADES AND GENERAL CONTRACTOR. VERIFY EXACT LOCATION OF EQUIPMENT TO BE FURNISHED BY OTHERS PRIOR TO ROUGH-IN. COORDINATE LOCATION AND INSTALLATION OF OWNER-FURNISHED ITEMS AFFECTING THIS TRADE.
- 10. ALL WIRING SHALL BE IN CONDUIT. MC-TYPE CABLE MAY BE USED FOR INTERIOR BRANCH CIRCUIT WIRING IF ALLOWED BY THE AUTHORITY HAVING JURISDICTION. ALL WIRING SHALL BE #12 AWG MINIMUM COPPER CONDUCTORS. ALUMINUM CONDUCTORS WILL NOT BE ALLOWED.
- 11. FEEDER CONDUCTORS, BRANCH WIRING, PANEL BUSS AND GROUND BUSS SHALL BE COPPER, UNLESS NOTED OTHERWISE.
- 12. ELECTRICAL DISTRIBUTION EQUIPMENT SHALL BE GENERAL ELECTRIC, EATON, SQUARE D OR SIEMENS.
- 13. ELECTRICAL CONTRACTOR SHALL ASSIGN CIRCUITS IN FIELD ON ALL PANELBOARDS TO MAKE LOADS ON EACH PHASE AS BALANCED AS POSSIBLE.
- 14. ELECTRICAL CONTRACTOR SHALL ASSEMBLE AND PROVIDE TO THE OWNER AS PART OF CLOSE-OUT SUBMISSION REQUIREMENTS, ORGANIZED BINDER WITH TECHNICAL DATA, CUT SHEETS, MAINTENANCE REQUIREMENTS, ADJUSTMENT PROCEDURES, TEST REPORTS, APPROVALS, WARRANTIES, PHONE NUMBERS OF SERVICE PERSONNEL, SOURCES OF REPLACEMENT PARTS AND OTHER PERTINENT INFORMATION.
- 15. BEFORE BEGINNING EXCAVATIONS OR DEMOLITION OF ANY NATURE WHATSOEVER, CONTRACTOR SHALL LOCATE ALL SERVICES AND UTILITIES OCCURRING WITHIN THE BOUNDS OF THE PROJECT. THE CONTRACTOR SHALL THEN PROCEED WITH CAUTION IN HIS WORK SO THAT NO UTILITY OR LINE SERVING AREAS THAT ARE TO REMAIN BE DAMAGED WITH A RESULTANT LOSS OF SERVICE. VERIFY THE SOURCE AND SERVICE OF EACH AND EVERY LINE ENCOUNTERED AND RECORD SERVICE, SIZE AND LOCATION ON RECORD DRAWINGS.
- 16. COORDINATE EACH AND EVERY INTERRUPTION OF SERVICES AND UTILITIES WITH THE OWNER AND UTILITY COMPANIES TO ENSURE MINIMUM SHUT-DOWN TIMES ARE ACCEPTABLE.
- 17. FOR EACH EQUIPMENT CONNECTION SHOWN, PROVIDE THE DEVICE, OUTLET, DISCONNECT SWITCH, OR JUNCTION BOX REQUIRED TO CONNECT THE EQUIPMENT.
- 18. NO SINGLE CONDUIT SHALL CONTAIN MORE THAN 6 CURRENT CARRYING CONDUCTORS, UNLESS NOTED OTHERWISE AND PROPERLY DERATED.
- 19. REVIEW ARCHITECTURAL, STRUCTURAL, CIVIL, MECHANICAL, PLUMBING, AND OTHER DRAWINGS PRIOR TO
- 20. INSTALL ALL MATERIALS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. ANY DEVIATIONS SHALL BE BROUGHT TO THE ARCHITECT/ENGINEER'S ATTENTION PRIOR TO INSTALLATION.
- 21. VERIFY EXACT LOCATIONS OF EXISTING AND NEW UNDERGROUND UTILITIES, PIPING, AND RACEWAY SYSTEMS PRIOR TO TRENCHING. PROVIDE NECESSARY TRENCHING, BACKFILL, EXCAVATION, SUPPORTS, SERVICE FEEDERS (CONDUIT AND/OR WIRE), PULLBOXES, TRANSFORMER PADS, SAWCUTTING AND PATCHING, CONCRETE/PAVING, ETC. REQUIRED. BACKFILL TRENCHES TO 90% COMPACTION AND PATCH TO MATCH EXISTING. CONTRACTOR SHALL OBTAIN AND VERIFY EXACT UTILITY COMPANY DRAWINGS AND REQUIREMENTS.
- 22. SEE PLUMBING AND MECHANICAL DRAWINGS FOR ALL DIVISION 22 AND 23 EQUIPMENT LOCATIONS AND ELECTRICAL LOAD REQUIREMENTS.
- 23. ELECTRICAL CONTRACTOR TO PROVIDE MEANS (REQUEST AND INSTALLATION OF) TEMPORARY CONSTRUCTION POWER.

E-0-00 ELECTRICAL GENERAL NOTES
E-1-01 ELECTRICAL DEMOLITION PLAN
E-1-02 ELECTRICAL PLAN
E-5-01 ELECTRICAL ONE LINE DIAGRAM

E-6-01 ELECTRICAL SCHEDULES

REVISION DESCRIPTION	ISSUE FOR PERMIT	ISSUED FOR CONSTRUCTION					
DATE	11/27/2020	12/04/2020					
ВУ							
REV. NO.							


ENGINEERING CONSULTANTS

8500 Bluffstone Cove, Suite B-103
Austin, Texas 78759 | 512.338.1101




IF A DE

	DED	
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		



E-0-00



ELECTRICAL - DEMOLITION - LEVEL 1

SCALE: 1/4"=1'-0"

KEYED NOTES


DISCONNECT AND REMOVE EXISTING TRUCK WASH EQUIPMENT FROM ELECTRICAL SYSTEM IN WHOLE ROOM. REMOVE CONDUIT AND CONDUCTORS BACK TO PANELS.

2. DISCONNECT AND REMOVE EXISTING TRANSFORMER TXFMR-HW-KVA30.


DEMOLITION NOTES

A. REFER TO GENERAL NOTES ON SHEET E-0-00 FOR ADDITIONAL INFORMATION.

	DED	
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		
REVIEWED BY		



E-1-01



NOTES

- A. REFER TO GENERAL NOTES ON SHEET E-0-00 FOR ADDITIONAL INFORMATION.
- B. CIRCUIT BREAKER SHALL SERVE AS DISCONNECTING MEANS FOR EQUIPMENT WITHIN 50 FT AND IN SIGHT OF PANELBOARD.
- C. CONDUIT TO FAR BAY SHALL BE ROUTED THROUGH WALL AND OVER ROOF SO AS TO NOT OBSTRUCT WASH EQUIPMENT. PROVIDE CONDUIT WITH PULL STRINGS FOR INSTALLATION OF CONTROL WIRES BY OTHERS UNLESS NOTED OTHERWISE.

| FeV. BY DATE REVISION DESCRIPTION | NO. BY DATE | REVISION DESCRIPTION | 11/27/2020 | ISSUE FOR PERMIT | SSUE FOR CONSTRUCTION | SSUE FIRM | SSOO BIUffstone Cove, Suite B-103 | Austin, Texas 78759 | 512.338.1101 | Project No.: 20049.MS.AUS | Project No.

ENGINEERING SERVICES DEPARTMENT
KGSC TRUCK WASH FACILITY
PROPOSED IMPROVEMENTS


LEVEL

NEW

ELECTRICAL

OF A COUNDED 1999

34 []	DED	
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		
REVIEWED BY		




E-1-02


	<u> </u>	<u> </u>			
				TRUCK WASH STATION	
				i I	
	TRUCK WASH STATION				
	TRUCK WASH STATION				
				(11)——	
				_	
	$\vartheta$ .				
				į	
	(11)			i i	
			13		
		12			
LW1-13	LW-19/21/23				
	<b>¥</b> √10)				
	WP 60A/3P/N4X	M2 A			
	<b>*</b> '			·///////  !	
X/////////////////////////////////////	$\Phi$	QQQQQ EVO CHEM. PANEL Q	AO BOX O		
	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	S WATER	BLASTER AANV/TON /15AND	<u> </u>	
	HW-13/15/17	予 \ \ \ * \ HW-2/4/6	"L X 28"W X 79"H WATER STORAGE TANK	WATER WATER	
	HW1-2/4/6 HW-19/21/23 HW1-8/10/2	HW1-14/16/18 HW-8/10/12		6 HW1-7/9/11 HW1-1/3/5 WALER SOFTENER LW-8 HW1-1	(8) 13/15/17
	HW-19/21/23 HW1-8/10/2	HW1-14/16/18 \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	34/36	HW-38/40/42	
	$\frac{\text{HW}'-19/21/23}{4}$ $\frac{\text{HW}1-8/10/2}{3}$	\ 1000000000000000000000000000000000000	HW-25/27/29		
		NW-20/22/24 HW-26/28/30	LW1-11	v T1 🕏	
	EXISTING LW1	·	₹		
		•	EXISTING LW	EXISTING HW NEW HW1	
		<u> </u>	Ψίνι		
					_
		EXISTING SERVICE ————————————————————————————————————			
CTRICAL - NEW - LEVEL	1	DISTRIBUTION PANEL			
ZIINIOINE INEVV EEVEE	<u> </u>				

		GROUNDING ELECTRODE	CONDUCTOR CU WIRE SIZE FOR:					
DESIGNATION RANGE (ID)	GROUND ROD	CONCRETE-ENCASED ELECTRODE	STRUCTURAL STEEL AND METAL WATER PIPING (IF ANY)					
20G-100G	#8	#8	#8					
125G-150G	#6	#6	#6					
175G-200G	#6	#4	#4					
225G-300G	#6	#4	#2					
350G-500G	#6	#4	#1/0					
600G-800G	#6	#4	#2/0					
1000G+	#6	#4	#3/0					
NOTES:	1. DESIGNATIO THE 20G-100G		ED BY A "G." FOR EXAMPLE, 30G WOULD FALL WITHIN					
	GROUNDING EI	CONDUCTOR CONNECTED TO FIRST ELECTRODE IN SYSTEM SHALL BE SIZED ACCORDING TO THE GROUNDING ELECTRODE REQUIRING THE LARGEST CONDUCTOR. ONLY AVAILABLE GROUNDING ELECTRODES SHALL BE CONSIDERED. ALL BONDING BETWEEN REMAINING ELECTRODES SHALL BE SIZED ACCORDING TO VALUE LISTED IN TABLE.						
	3. GROUNDING	ELECTRODE SYSTEMS SHALL CON	SIST OF ALL AVAILABLE GROUNDING ELECTRODES.					
	4. THIS TABLE	S BASED ON ARTICLE 250.66 OF TH	HE NEC.					

				FEEDER A	AND BRANCH	CIRCUIT SCHEI	DULE
MARK	# OF SETS	PHASE & NEU. CONDUCTORS (CU)	EQUIP. GRND CONDUCTOR (CU)	3PH / 4W CONDUIT SIZE	1 OR 3PH / 3W CONDUIT SIZE	1PH / 2W CONDUIT SIZE	NOTES:
20	1	#12	#12	3/4"	3/4"	3/4"	A. FEEDER AND BRANCH CIRCUIT SCHEDULE IS BASED ON NEC TABLE 310.15(B)(16) AND TABLE 250.122.
25	1	#10	#10	3/4"	3/4"	3/4"	,
30	1	#10	#10	3/4"	3/4"	3/4"	B. ALL NEUTRAL CONDUCTORS SHALL MATCH THE SIZE OF THE PHASE CONDUCTORS UNLESS OTHERWISE NOTED.
35	1	#8	#10	3/4"	3/4"	3/4"	
40	1	#8	#10	1"	3/4"	3/4"	C. FEEDER AND BRANCH CIRCUIT SCHEDULE IS NOT TO BE USED FOR SIZING SERVICE FEEDERS BEFORE MAIN
45	1	#8	#10	1"	3/4"	3/4"	OVERCURRENT PROTECTION EQUIPMENT.
50	1	#8	#10	1"	1"	3/4"	D. FEEDER AND BRANCH CIRCUIT MARK LEGEND
55	1	#6	#10	1-1/2"	1-1/2"	1"	
60	1	#6	#10	1-1/2"	1-1/2"	1"	100 - 4 (NG, IF SHOWN = NO GND)
70	1	#4	#8	1-1/2"	1-1/2"	1"	1
80	1	#4	#8	1-1/2"	1-1/2"	1"	CIRCUIT MARK _ NUMBER OF PHASE
90	1	#3	#8	1-1/2"	1-1/2"	1"	SEE FEEDER AND CONDUCTORS
100	1	#3	#8	2"	1-1/2"	1-1/2"	BRANCH CIRCUIT 4 = 3 PH / 4 WIRE SCHEDULE FOR 3 = 1 OR 3 PH / 3 WIRE
125	1	#1	#6	1-1/2"	1-1/2"	N/A	CONDUCTOR AND 2 = 1 PH / 2 WIRE
150	1	#1/0	#6	2"	1-1/2"	N/A	CONDUIT SIZE
175	1	#2/0	#6	2"	2"	N/A	
200	1	#3/0	#6	2-1/2"	2"	N/A	
225	1	#4/0	#4	2-1/2"	2"	N/A	
250	1	250 KCMIL	#4	3"	2-1/2"	N/A	
300	1	350 KCMIL	#4	3"	3"	N/A	
350	2	#2/0	#3	2"	2"	N/A	
400	2	#3/0	#3	2-1/2"	2"	N/A	
500	2	250 KCMIL	#2	3"	2-1/2"	N/A	
600	2	350 KCMIL	#1	3"	3"	N/A	
800	3	300 KCMIL	#1/0	2-1/2"	2-1/2"	N/A	1
1000	3	400 KCMIL	#2/0	4"	3"	N/A	1
1200	4	350 KCMIL	#3/0	3"	3"	N/A	
1600	5	400 KCMIL	#4/0	4"	4"	N/A	
2000	6	400 KCMIL	250 KCMIL	4"	N/A	N/A	
2500	7	500 KCMIL	400 KCMIL	4"	N/A	N/A	
3000	8	500 KCMIL	400 KCMIL	4"	N/A	N/A	
3500	10	500 KCMIL	500 KCMIL	4"	N/A	N/A	
4000	10	600 KCMIL	500 KCMIL	4"	N/A	N/A	



ELECTRICAL ONE LINE DIAGRAM
N.T.S.



ENCOTECH ENGINEERING CONSULTANTS

CITY OF AUSTIN, TX
DEPARTMENT OF PUBLIC WORKS
ENGINEERING SERVICES DEPARTMENT
KGSC TRUCK WASH FACILITY
PROPOSED IMPROVEMENTS

ONE LINE DIAGRAM

RICAL

"		
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		



E-5-01

	PAN	NELBOARD SCHEE	DULE	E	XIS	ΓING	<u>HW</u>				LOCATION: C.B. RATING:	EQUIPMENT ROOM 35 K.A.I.C.		
	T	VOLTAGE	PHASE	WIR	E		MOUNTING		Bl	JS (A)	LUG	TYPE	T	
WIRE SIZE	Y P	480Y/277V	3	4			SURFACE			400	MLO	NEMA 4X	] Y	WIRE SIZE
	Ē	USE and/or AREA	SERVED	C/B POLE	CIR	ØΑ	LOAD ØB	ØС	CIR	C/B POLE	USE and/o	or AREA SERVED	Ē	
		WASH BAY, MECH RN	M LIGHTING	20/1	1_	1500 1142			2	20/3	CHEM	PUMP, 1HP		
		WASH BAY LIGI	HTING	20/1	3		1000 1142		4					
		EXTERIOR LIGH	ITING	20/1	5			500 1142	6					
		XFMR TLW	V	100/3	7	9398 1142		1172	8	20/3	CHEM	CHEM PUMP, 1HP		
					9	1142	11498							
					11		1142	9014	10					
		PUMP STAN	ND	20/3	13	4352		1142	12	20/3	CHEM	PUMP, 3/4HP		
		' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '		20,3	15	870	4352		14	20,5		. O.V , 3, 4		
					17		870	4352	16					
		211242 6742		20.42	19	4352	1	870	18	20/2			-	20.0
		PUMP STAN	ND	20/3	21	5984	4352		20	30/3	HP3 P	UMP, 7.5HP		30-3
							5984	4252	22					
					23		1	4352 5984	24					
		WATER BLAS	TER	20/3	25	3808 5984			26	30/3	HP3 P	UMP, 7.5HP		30-3
					27		3808 5984		28					
					29			3808 5984	30					
100-4		PANEL HW	/1	100/3	31	20889 5984			32	30/3	HP3 P	UMP, 7.5HP		30-3
					33	3301	20889 5984		34					
					35		J 304	20889	36					
		SPACE			37	-	]	5984		20/3	WTI	R RECLAIM		
					39	4134	-		38	, -				
					41		4134	-	40					
		ITOTAL LOAD PER	PHASE			69539	71139	4134 <b>68155</b>	42		71139 V <i>A</i>	A / 277 V = 257 A		
① GF	Cl	② AFCI ③ AFCI/G		HUNT TRIF	)			) LOCKABLE	(	OPTIONS:		TO SPECIFICATIONS		
	FEE	DER OCPD AND C	CONDUCT	OR CA	LCU	LATION								
		DESCRIPTION		CONNEC		DEMAND	DEMAND	LOAD	FEED	ER LOAD	NOTES			
		TING		LOAD		FACTOR 1.00	LOAD	MULTIPLIER		2.75				
		EPTACLES		3.00 1.08		1.00 50%>10	3.00 1.08	1.25 1.00	l	3.75 1.08				
		SEST MOTOR		17.9		1.00	1.08 17.95	1.25	l	22.44				
		ER MOTOR(S)		184.7		1.00	184.70	1.00	ı	84.70				
	HEAT			1.58	3	1.00	1.58	1.25	] :	1.98				
	CON	TINUOUS LOADS		0.02	2	1.00	0.02	1.25	(	0.03				
	NON	ICONTINUOUS LOADS		0.50		1.00	0.50	1.00	l	0.50				
		HEN EQUIPMENT	QTY = 0	0.00		1.00	0.00	1.00	l	0.00				
		RSIFIED LOAD		0.00		1.00	0.00	0.50	_	0.00				
	TOTAL KVA 208.83				33	-	-	-	1 2º	14.47	I			
		AL AMPS		251					l	258 A				

	PAN	IELBOARD SCHED	ULE				HW1				LOCATION: C.B. RATING:	EQUIPMENT ROOM 35 K.A.I.C.		
	Т	VOLTAGE	PHASE	WIR	RΕ		MOUNTING		ВІ	US (A)	LUG	TYPE	Т	
WIRE	Υ	480Y/277V	3	4			SURFACE			100	MLO	NEMA 4X	Y	WIRE
SIZE	P E	USE and/or AREA	SERVED	C/B POLE	CIR	<i>d</i> .	LOAD		CIR	C/B POLE	<b>†</b>	or AREA SERVED	P E	SIZE
		3430C PRESSURE V		20/3	1	ØA 3264 4352	ØВ	ØС	2	20/3	PUMP STAND		+ -	
					3	4352	3264	]		1				
					5		4352	3264	4					
	24222 PDESSURE WASHED			22.62	7	3264	1	4352	6	(-				
		3430C PRESSURE V	WASHER	20/3	9	4352	2264	1	8	20/3	PUI	MP STAND		
							3264 4352		10					
					11		-	3264 4352	12					
		ROLAIR AIR COMP	RESSOR	20/3	13	1305 4352			14	20/3	PUN	MP STAND		
					15		1305 4352		16					
					17		+332	1305 4352						
					19	-	]	<u> 4332</u>	18					
					21	-	-	]	20					
					23		-	-	22					
		CDA CE			25	-	1	-	24	]		CD A CE		
	SPACE				27	-	_	1	26	1		SPACE		
						-		28						
					29		-	-	30					
					31	-			32					
					33		-		34					
					35			-	36					
					37	-	]			]				
					39	-	-	]	38					
					41		-	-	40					
		TOTALLOAD DED	DUACE			20000	20000	20000	42		20000 1/	A / 277 V = 75 A		
① GF	·Cl	TOTAL LOAD PER  ② AFCI ③ AFCI/GF		HUNT TRIF		<b>20889</b> (5) SWD (	<b>20889</b> 6) HACR (7	20889 DIOCKABLE		ODTIONS		A / 277 V = 75 A		
<u>(1)</u> GF	·u	2) AFCI (3) AFCI/GF		HUNI IKI		(3) 3WD (	b) HACK (	LOCKABLE	,	JPHONS:	NONE - REFER	TO SPECIFICATIONS		
	FEE	DER OCPD AND C	ONDUCT	OR CA	LCU	LATION								
		DESCRIPTION		CONNEC		DEMAND	DEMAND	LOAD	EEEU	ER LOAD	NOTES			
		IN KVA)		LOAI	)	FACTOR	LOAD	MULTIPLIER	11111	ZIN LOAD	NOTES			
	LIGH			0.00		1.00	0.00	1.25		0.00				
		PTACLES		0.00		50%>10	0.00	1.00		0.00				
	LARGEST MOTOR			13.0		1.00	13.06	1.25		16.32				
	OTHER MOTOR(S) HEATING			49.6 0.00		1.00	49.61	1.00		19.61 0.00				
				0.00		1.00 1.00	0.00 0.00	1.25 1.25		0.00				
	NONCONTINUOUS LOADS 0.00				1.00	0.00	1.25		0.00					
	KITCHEN EQUIPMENT QTY = 0 0.00				1.00	0.00	1.00		0.00					
		RSIFIED LOAD		0.00		1.00	0.00	0.50		0.00				
TOTAL KVA 62.67				t		-	-	-		55.93				
	TOTAL AMPS 75 A													

	PAN	NELBOARD SCHE	DULE	E	XIS	ΓING	<u>LW</u>				LOCATION: C.B. RATING:	EQUIPMENT ROOM 22 K.A.I.C.		
	Т	VOLTAGE	PHASE	WIR	RE		MOUNTING	i	В	US (A)	LUG	TYPE	Т	
WIRE	Y	208Y/120V	3	4			SURFACE		_	150	MLO	NEMA 4X	Y	WIR
SIZE	P E	USE and/or AREA	SERVED	C/B POLE	CIR	ØA	LOAD ØB	ØC	CIR	C/B POLE	USE and/	or AREA SERVED	P E	SIZE
		EXT RECEPTA	CLE	20/1	1	180 540			2	20/1		RCPT		
		WTR RECLAIM	CNTL	20/1	3	340	500	]	4	20/1		SPARE		
		SPARE		20/1	5		_	-	6	20/1		SPARE		
		MECH ROOM	RCPT	20/1	7	180	]		8	20/1	WAT	ER SOFTENER		
		MECH ROOM RCPT	& HEATER	20/1	9	20	380	]	10	20/1		SPARE		
		SPARE		20/1	11		-	-		20/1		SPARE		
		MECH ROOM	IGFI	20/1	13	180	]	-	12	20/1		SPARE	+	
		SPARE		20/1	15	-	-	]	_14	20/1		SPARE	+	
		HEATER		20/1	17		-	200	16	20/1		SPARE	+	
45-3		TROLLEY		45/3	19	3993	]	_	18	20/1		SPARE		
43-3		INOLLEY		43/3	21	-	3993	1	20	20/1		SPARE	+	
					23		-	3993	22	-			+	
		A O POV		25/2	25	4125	1	-	24	20/1		SPARE	+	
		AO BOX		35/3	27	-	4125	1	26	20/1		SPARE	_	
					29		-	4125	28	20/1		SPARE		
							1	- 4123	30	20/1		SPARE	4	
		SPARE		20/1	31	-	-	٦	32	20/1		SPARE		
		SPARE		20/1	33		1000	_	34	20/1	HE	EAT TRACE		
		SPARE		20/1	35		-	-	36	20/1		SPARE		
		SPARE		20/1	37	- 180		-	38	100/3	P/	ANEL LW1		
		SPARE		20/1	39		1500		40					
		SPARE		20/1	41			- 696	42					
		TOTAL LOAD PER	PHASE			9398	11498	9014			11498 V	/A / 120 V = 96 A		
① GF	CI	② AFCI ③ AFCI/G	FCI 4 S	HUNT TRII	Р	⑤ SWD (	6 HACR (	DLOCKABLE	(	OPTIONS:	NONE - REFER	TO SPECIFICATIONS		
	FEE	DER OCPD AND (	CONDUCT	OR CA	LCU	LATION			•					
		DESCRIPTION		CONNEC		DEMAND	DEMAND	LOAD	FEEC	ER LOAD	NOTES			
	LIGH	O IN KVA)		LOAI		FACTOR	LOAD	MULTIPLIER	_	0.00				
		PTACLES		1.00		1.00 50%>10	0.00 1.08	1.25 1.00	1	0.00 1.08				
		SEST MOTOR		12.3		1.00	12.38	1.25	1	15.47				
	OTHER MOTOR(S)			14.3		1.00	14.36	1.00	1	14.36				
	HEATING		1.5	8	1.00	1.58	1.25		1.98					
	CONTINUOUS LOADS		0.03	2	1.00	0.02	1.25		0.03					
		CONTINUOUS LOADS		0.50		1.00	0.50	1.00	1	0.50				
		HEN EQUIPMENT	QTY = 0	0.00		1.00	0.00	1.00	1	0.00				
	DIVERSIFIED LOAD 0.00				1.00	0.00	0.50	_	0.00					
	TOT '	TOTAL KVA 29.91			)1	-	_	-		33.40				


	PAN	IELBOARD SCHED	ULE	Е	XIST	ΓING	<u>LW1</u>		LOCATION: <u>EQUIPMENT ROOM</u> C.B. RATING: <u>10 K.A.I.C.</u>					
	Т	VOLTAGE	PHASE	WIRE			MOUNTING		BUS (A)		LUG TYPE		Т	
WIRE SIZE	Y P	208Y/120V	3	4			SURFACE			100	MLO	NEMA 4X	Y P	WIRI SIZE
SIZL	E	USE and/or AREA	SERVED	C/B POLE	CIR	ØΑ	LOAD ØB	ØС	CIR	C/B POLE	USE and/o	or AREA SERVED	Ę	3121
					1	-			2	20/1		SPARE		
					3		-		4	20/1		SPARE		
		SPACE			5	1		-	6	20/1		SPARE		
					7	-			8	20/1		SPARE		
					9	-	- 1500	]	10	20/1	OUTDO	OOR VACUUM		
		EXHAUST FA	N	20/1	11		1500	696	12	20/1		SPARE		
		RCPT		20/1	13	180		-		20/1		SPARE		
		SPARE		20/1	15	-	-	]	14	, -				
		SPARE		20/1	17		-	-	16					
		SPARE		20/1	19	-		-	18					
	SPARE			20/1	21	-	-	]	20			SPACE		
		SPARE			23		-	-	22			SI ACE		
		SPARE		20/1	25	-		-	24					
		SPARE		20/1	27	-	-	]	26	-				
		SPARE		20/1	29		-	-	28	-				
			DUACE	20/1		100	4500	-	30		1500.77	\		
		TOTAL LOAD PER				180	1500	696			1300 V <i>F</i>	A / 120 V = 13 A		
① GF	CI	② AFCI ③ AFCI/GF	CI (4) S	HUNT TRI	•	(5) SWD (6	6 HACR (7	) LOCKABLE	(	OPTIONS:	NONE - REFER	TO SPECIFICATIONS		
	FEE	DER OCPD AND C	ONDUCT			LATION								
		DESCRIPTION IN KVA)		CONNEC LOAI		DEMAND FACTOR	DEMAND LOAD	LOAD MULTIPLIER	FEEC	DER LOAD	NOTES			
	LIGH			0.00		1.00	0.00	1.25		0.00				
		PTACLES		0.00		50%>10	0.00	1.00		0.00				
		SEST MOTOR		1.50 0.88		1.00	1.50	1.25		1.88 0.88				
	HEAT	ER MOTOR(S) TNG		0.00		1.00 1.00	0.88 0.00	1.00 1.25		0.00				
		TINUOUS LOADS		0.00		1.00	0.00	1.25		0.00				
		CONTINUOUS LOADS		0.00		1.00	0.00	1.00		0.00				
	KITCH	HEN EQUIPMENT	QTY = 0	0.00	)	1.00	0.00	1.00		0.00				
		RSIFIED LOAD		0.00		1.00	0.00	0.50	<del>                                     </del>	0.00				
	TOTAL KVA 2.			2.38	3	-	-	-	l	2.75				
	TOTAL AMPS			7 A						8 A				

REVISION DESCRIPTION	ISSUE FOR PERMIT	ISSUED FOR CONSTRUCTION					
DATE	11/27/2020	12/04/2020					
ВУ							
REV. BY NO.							




CITY OF AUSTIN, TX
DEPARTMENT OF PUBLIC WORKS
ENGINEERING SERVICES DEPARTMENT
KGSC TRUCK WASH FACILITY
PROPOSED IMPROVEMENTS

ELECTRICAL SCHEDULE



/		
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		
REVIEWED BY		



E-6-01

#### **MECHANICAL ABBREVIATIONS** CONDITIONING ABOVE FINISHED FLOOR HOT WATER HOT WATER RETURN \_ H.W.R. ABOVE FINISHED GRADE AFG. HERTZ **ADDENDUM** ADD. **ADJUSTABLE** ADJ. AIR CONDITIONING A/C **INFORMATION** INFO. AIR HANDLER UNIT AHU **INCHES** APPROX APPROXIMATE(LY) INSULATION INSUL ARCHITECT(URAL) ARCH('L) INTERIOR AUTO **AUTOMATIC AUXILIARY** AUX. **KILOWATT** KW LEAVING AIR TEMPERATURE BLDG. BUILDING LEAVING **BOTTOM OF DUCT** BOD LOUVER BOTTOM OF PIPE BOP LONG RADIUS ELBOW **BRITISH THERMAL UNIT** BTU. CAPACITY MFR. MANUFACTURE(R) CARBON DIOXIDE \_CO2 MA. MAKEUP AIR CTR. **CENTER** MAX. MAXIMUM CIRCLE CIR. MBH. 1,000 BTU/HR CONDENSATE DRAIN MAXIMUM OVERCURRENT MOCP **CONDENSING UNIT** \_C.U. CONST PROTECTION CONSTRUCTION MECH. **MECHANICAL** CONTINUATION CONT. MTL. METAL COOLING CLG. MINIMUM MIN. **CUBIC FOOT PER MINUTE** CFM MIXED AIR TEMPERATURE MAT. MISCELLANEOUS DMPR MOTORIZED VOLUME DAMPER MVD DEGREE FAHRENHEIT DegF. MULT. MULTIPLE DEMOLISH(ITION) DEMO. MANUAL VOLUME DAMPER VD. DIAMETER DIA. **DIRECT EXPANSION** DIV. DIVISION NOT APPLICABLE DN. DOWN NC. NOISE CRITERIA DBL. DOUBLE NAT. NATURAL DRAWING(S) DWG(S). NOMINAL NOM. DRY BULB D.B. NORTH **DUCTLESS SPLIT** NOT IN CONTRACT N.I.C. N.T.S. NOT TO SCALE **EXISTING** NUMBER NO./# ENTERING AIR TEMPERATURE EAT. OUTSIDE AIR OA **EFFICIENCY** ELECTRIC(AL) ELEC. ELEVATION PARTIAL PART ENERGY EFFICIENCY RATIO EER. PHASE **ENGINEER** ENGR. POLYVINYL CHLORIDE **ENTERING** ENT POUND(S) EQUAL POUNDS PER SQUARE INCH **EQUIPMENT** EQPT. PRESSURE DROP ETC. ETCETERA **EXHAUST FAN** QUANTITY QTY. **EXISTING** EXIST. **EXPOSED** EXP. **RADIUS EXHAUST** EXH. REFRIGERATION REFRIG. EXHAUST AIR REC. RECESSED EXTERNAL REINFORCE(ING)(ED)(MENT) EXTERNAL STATIC PRESSURE ESP. REINF. RETURN AIR REQ.('D) REQUIRE(D) **FARENHEIT ROOF TOP UNIT** RTU FINISH(ED) FIN.('D) ROOM FINISH FLOOR FLEXIBLE FLEX SANITARY SEWER **FLOOR** SCHEDULE FOOT/FEET SEASONAL ENERGY EFFICIENCY SEER RATIO **GALLONS PER MINUTE** SECTION GALVANIZED GALV. SENS. SENSIBLE GAS HEATER SMOKE DETECTOR S.D. GAUGE SOUTH **GENERAL CONTRACTOR** SPECIFICATION(S) SPEC.('S) **GROUND GND** GYPSUM BOARD

NOTE: NOT ALL ABBREVIATIONS ON THIS LIST ARE APPLICABLE TO THIS PROJECT.

APPLICABLE CODES
2015 UMC
2012 IBC
2017 NEC
2015 IECC
2012 TAS

HEATING, VENTILATION & AIR HVAC

HEATER

HORSEPOWER

DESIGN CRITERIA	SUMMER	WINTER
OUTDOOR CONDITIONS BASED ON 1% ASHRAE	99	26
INDOOR CONDITIONS	75	72


# SQUARE **SQUARE FEET** STAINLESS STEEL **SQUARE FEET** STATIC PRESSURE SUCTION SUPPLY AIR **TEMPERATURE TEMP** TOP OF STEEL T.O.S. TYPICAL UNDERGROUND UNDERWRITER LABORATORIES U.L. **UNIT HEATER** UNLESS NOTED OTHERWISE U.N.O. UTILITY UTIL. MANUAL VOLUME DAMPER VOLTAGE VOLUME WATER GAUGE WEIGHT WEST WET BULB WITHOUT MECHANICAL DEMO SYMBOL LEGEND DEMO SUPPLY AIR GRILLE DEMO RETURN AIR GRILLE • DEMO EXHAUST AIR GRILLE ✓//// • CONDENSATE DRAIN PIPE ✓/ / MA / / • DEMO CHILLED WATER RETURN → DEMO CHILLED WATER SUPPLY → DEMO HOT WATER RETURN ✓ ✓ ✓ → DEMO HOT WATER SUPPLY '//// • EXISTING EQUIPMENT, DUCTWORK, DIFFUSERS, AND DAMPERS -/-/-/-/ • DEMOLITION DEMOLITION EQUIPMENT AHU-XX DEMO TERMINAL UNIT PIPING SYMBOL LEGEND

— CHWS — •	CHILLED WATER SUPPLY
— CHWR — •	CHILLED WATER RETURN
SWHH	HEATING HOT WATER SUPPLY
— HHVR — •	HEATING HOT WATER RETURN
— CD — •	CONDENSATE DRAIN
—— CHWR —— •	EXISTING CHILLED WATER RETURN
—— CHWS —— •	EXISTING CHILLED WATER SUPPLY
—— HHWR —— •	EXISTING HOT WATER RETURN
HHWS •	EXISTING HOT WATER SUPPLY


NOTE: NOT ALL SYMBOLS ON THIS LIST MAY BE APPLICABLE TO THIS PROJECT.

# DRAFTING SYMBOLS

#### PLAN/DETAIL DESIGNATION



# **ELEVATION MARK**



#### MECHANICAL CONTROLS SYMBOL LEGEND **MECHANICAL SYMBOL LEGEND**

 $\boxtimes$ 

TYPE/CFM

SUPPLY AIR GRILLE

EXHAUST AIR GRILLE

COMBINATION FIRE/SMOKE DAMPER

MOTORIZED VOLUME DAMPER

TAKEOFF WITHOUT DAMPER

TAKEOFF WITH DAMPER

SPIN-IN WITH DAMPER

WALL CAP / LOUVER

SPIN-IN WITHOUT DAMPER

→ • SIDEWALL GRILLE, SUPPLY AIR

SHOWN DASHED

RADIUS ELBOW

• DOUBLE WALL SPIRAL DUCT

CONNECT TO EXISTING

DISCONNECT FROM EXISTING

DIAMETER OF ROUND DUCT

TERMINAL UNIT

SUPPLY AIR DUCT UP

SUPPLY AIR DUCT DOWN

RETURN AIR DUCT DOWN

EXHAUST AIR DUCT DOWN

UNDERCUT DOOR FOR A

NOTE: NOT ALL SYMBOLS ON THIS LIST

MAY BE APPLICABLE TO THIS PROJECT.

1" MIN. CLEARANCE

EXHAUST AIR DUCT UP

PIPE DOWN

• PIPE UP

RETURN AIR DUCT UP

EXISTING DUCTWORK

NEW DUCTWORK

• SIDEWALL GRILLE, RETURN / EXHAUST AIR

MECHANICAL EQUIPMENT WITH

CONDENSING UNIT w/ CLEARANCES

TRANSITION RECTANGULAR TO ROUND DUCT

TURNINGVANE, 90 DEGREE ELBOW

• INCLINED RISE, IN DIRECTION OF AIR FLOW

• INCLINED DROP, IN DIRECTION OF AIR FLOW

##/## • NUMBER INDICATES WIDTH AND SECOND

SIZE OF RECTANGULAR DUCT WHERE FIRST

NUMBER INDICATES VERTICAL DIMENSION

CLEARANCES, SEE SCHEDULES


RETURN AIR GRILLE

THERMOSTAT

FIRE DAMPER

• FLEXIBLE DUCT WORK

• MANUAL DAMPER



 CURRENT SWITCH HAND-OFF-AUTO SWITCH

**AVERAGING TEMPERATURE** SENSOR SINGLE POINT

**TEMPERATURE** SENSOR SMOKE DETECTOR

LOW TEMPERATURE LIMIT SWITCH

> FILTER MOTOR

OPPOSED BLADE DAMPER

PARALLEL BLADE DAMPER MOTORIZED DAMPER

CHILLED WATER COIL **HEATING HOT** WATER COIL

**ELECTRIC RESISTIVE HEAT COIL** 

NOTE: NOT ALL SYMBOLS ON THIS LIST MAY BE APPLICABLE TO THIS PROJECT.

# **MECHANICAL GENERAL NOTES**

- A. THE MECHANICAL WORK CONSISTS OF PROVIDING LABOR, MATERIALS, PRODUCTS, AND IN PERFORMING ALL OPERATIONS REQUIRED FOR THE COMPLETE OPERATING INSTALLATION OF ALL MECHANICAL SYSTEMS IN ACCORDANCE WITH SPECIFICATIONS, APPLICABLE DRAWINGS, TERMS, CONDITIONS OF THE CONTRACT AND ALL APPLICABLE CODES AND ORDINANCES GOVERNING THE INSTALLATION OF THE VARIOUS MECHANICAL SYSTEMS. ALL WORK SHALL BE FULLY CORRELATED WITH THE WORK OF OTHER CRAFTS.
- B. EACH CONTRACTOR SHALL STUDY THE CONTRACT DOCUMENTS TO DETERMINE THE EXTENT OF WORK PROVIDED UNDER THIS CONTRACT, AS WELL AS TO ASCERTAIN THE DIFFICULTY TO BE ENCOUNTERED IN PERFORMING THE WORK ON THE DRAWINGS AND OUTLINED HEREINAFTER AND IN MAKING CONNECTIONS TO EXISTING UTILITIES, INSTALLING NEW EQUIPMENT AND SYSTEMS AND COORDINATING THE WORK WITH THE OTHER TRADES.
- C. EXAMINATION OF SITE: THE CONTRACTOR SHALL THOROUGHLY EXAMINE SITE AND SATISFY HIMSELF AS TO THE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED. THE CONTRACTOR SHALL VERIFY, AT THE SITE, ALL MEASUREMENTS AFFECTING HIS WORK AND SHALL BE RESPONSIBLE FOR THE CORRECTNESS OF SAME. NO EXTRA COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR FOR EXPENSES DUE TO HIS NEGLECT TO EXAMINE OR FAILURE TO DISCOVER CONDITIONS WHICH AFFECT HIS WORK. NO EXTRA COMPENSATION WILL BE ALLOWED ON ACCOUNT OF DIFFERENCES BETWEEN ACTUAL DIMENSIONS AND THOSE INDICATED ON THE DRAWINGS.
- D. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE MECHANICAL SYSTEMS AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.
- E. CONTRACT DOCUMENT DRAWINGS FOR MECHANICAL HVAC WORK IS DIAGRAMMATIC AND IS INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY. DO NOT SCALE DRAWINGS FOR EXACT LOCATION OF ITEMS
- INSTALL ALL MECHANICAL EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS, MANUFACTURER'S CERTIFIED DRAWING, CONTRACT DOCUMENTS, AND APPLICABLE CODES AND REGULATIONS.
- G. SHOULD DISCREPANCIES OCCUR WITHIN THE CONTRACT DOCUMENTS, THE MORE STRINGENT AND MORE COSTLY APPROACH SHALL APPLY FOR BIDDING PURPOSES THE CONTRACTOR IS TO NOTIFY THE OWNER'S REPRESENTATIVE OF DISCREPANCIES FOR CLARIFICATION. CLARIFICATIONS ISSUED AFTER THE CONTRACT IS AWARDED ARE TO BE INCORPORATED BY THE CONTRACTOR AT NO ADDITIONAL COSTS AND ARE TO BE REVIEWED BY THE OWNER'S REPRESENTATIVE TO DETERMINE IF A REDUCTION IN COST IS JUSTIFIED.
- THE CONTRACTOR SHALL OBTAIN ALL PERMITS AND PAY ALL FEES AND CHARGES TO ALL LOCAL AND OTHER RELATED AGENCIES AS REQUIRED.
- COORDINATE CONSTRUCTION OF ALL MECHANICAL WORK WITH ARCHITECTURAL STRUCTURAL, CIVIL, ELECTRICAL, PLUMBING WORK, ETC., SHOWN ON OTHER CONTRACT DOCUMENT DRAWING.
- J. CONCRETE HOUSEKEEPING PADS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR. IT SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR TO COORDINATE THE SIZE AND LOCATION OF CONCRETE HOUSEKEEPING PADS WITH THE GENERAL CONTRACTOR
- MECHANICAL CONTRACTOR SHALL COORDINATE ANY ROOF PENETRATION WITH ROOFING CONTRACTOR, ROOF SYSTEM MANUFACTURER, ARCHITECT, AND ALL OTHER TRADES INVOLVED. ALL ROOF PENETRATIONS SHALL BE REVIEWED AND APPROVED BY ROOF SYSTEM MANUFACTURER TO COMPLY WITH THE ROOFING
- MECHANICAL CONTRACTOR SHALL COORDINATE LOCATIONS AND SIZES OF ALL FLOOR AND WALL PENETRATIONS AND SHALL BE COORDINATED WITH STRUCTURAL, PLUMBING, ELECTRICAL, AND ARCHITECTURAL WORK.

#### **HVAC GENERAL NOTES**

- A. COORDINATE DIFFUSER, REGISTER, AND GRILLE LOCATIONS WITH ARCHITECTURAL REFLECTED CEILING PLANS, LIGHTING, AND OTHER CEILING ITEMS AND MAKE MINOR DUCT MODIFICATIONS TO SUIT.
- B. ALL DUCTWORK SHALL BE COORDINATED WITH ALL TRADES INVOLVED. OFFSETS IN DUCTS, INCLUDING DIVIDED DUCTS AND TRANSITIONS AROUND OBSTRUCTIONS, SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.
- C. PROVIDE ACCESS DOORS IN DUCTWORK TO PROVIDE ACCESS FOR ALL ITEMS AND EQUIPMENT LOCATED IN THE DUCTWORK THAT REQUIRE SERVICE AND/OR INSPECTION.

#### **DEMOLITION GENERAL NOTES**

- A. THE CONTRACTOR SHALL THOROUGHLY EXAMINE SITE AND SATISFY HIMSELF AS TO THE CONDITIONS UNDER WHICH THE DEMOLITION WORK IS TO BE PERFORMED. VERIFY ALL MECHANICAL ITEMS AND EQUIPMENT TO BE REMOVED PRIOR TO COMMENCING WORK.
- B. THE CONTRACTOR IS TO CONFIRM WITH THE OWNER WHICH EQUIPMENT DESIGNATED TO BE DEMOLISHED IS TO BE TURNED OVER TO THE OWNER AND WHICH ARE TO BE LEGALLY DISPOSED OF.

#### **SHEET INDEX**

M-0-00 MECHANICAL GENERAL NOTES MECHANICAL FLOOR PLAN - HVAC M-1-01

M-4-01 MECHANICAL SCHEDULES, DETAILS, AND CONTROLS

KGS PRC

OTF.

Z

0


EC

NOTES	NAME	DATE
CLIDVEV DV		
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		



M-0-00

**REVIEWED BY** 



# GENERAL SHEET NOTES

A. REFER TO GENERAL NOTES ON SHEET M-0-00 FOR ADDITIONAL INFORMATION.

# -> KEYED NOTES

- 1. EXISTING UNIT HEATER TO REMAIN.
- 2. PROVIDE IN-LINE EXHAUST FAN WITH INTEGRAL BACKDRAFT DAMPER ABOVE CEILING SUPPORTED FROM TOP OF STRUCTURAL BEAM. REFER TO DETAIL 1/M-4-01.
- . PROVIDE 14"Ø EXHAUST DUCT FROM INLINE EXHAUST FAN, TERMINATING 3'-0" BELOW CEILING. PROVIDE WITH 3/4" WIRE MESH SCREEN AT DUCT INLET.
- PROVIDE DOOR LOUVER FOR OUTSIDE AIR INTAKE LOUVER LOW IN WALL. MOUNT BOTTOM EDGE OF LOUVER AT 2'-0" A.F.F. REFER TO SCHEDULE.
- PROVIDE EXHAUST AIR LOUVER HIGH IN WALL, FITTED WITHIN 8" GAP ALONG TOP OF WALL. COORDINATE EXACT LOUVER WITH AND HEIGHT WITH ACTUAL WALL CMU CONSTRUCTION. REFER TO SCHEDULE.
- PROVIDE 10" DIAMETER FLUE FROM GAS FIRED PRESSURE WASHER EQUIPMENT UP TO ROOF MOUNTED FLUE. COORDINATE EXACT CONNECTION LOCATION WITH MANUFACTURER REQUIREMENTS. REFER TO FLUE DETAIL 2/M-4-01


ISION DESCRIP	ISSUE FOR PERMIT	<b>UED FOR CONSTRUC</b>			
ISION DES	ISSUE FOR F	JED FOR CON			

ENCOTECH ENGINEERING CONSULTANTS

FLOOR PLAN

MECHANICAL

	DED 183	
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		



MECHANICAL FLOOR PLAN - HVAC

SCALE: 1/8"=1'-0"




	EXHAUST FAN SCHEDULE															
MARK AREA SERVED	AREA SERVED	LOCATION	INTERLOCK	AIR DATA				ELECTRICAL DATA			UNIT DATA					
IVIANN	ARLA SERVED	LOCATION	INTERLOCK	CFM	S.P.	HP	RPM	FLA	MOCP	VOLT/PH	MAKE	MODEL	TYPE	DRIVE	LBS.	NOTES
EF-1	EQUIPMENT ROOM	CEILING	CONTINUOUS	880	0.3	0.22	1,083	4.8	15	115V/1PH	GREENHECK	CSP-A1050-VG	INLINE	DIRECT VARIABLE	49	DISC, SC, BDD, PP, VI
IOTES:  DISC = DISCONNECT SWITCH  TD = PROVIDE AND INSTALL A TIME-DELAY-OFF RELAY SWITCH TO ALLOW FAN TO C  SC = EC MOTOR  BDD = BACKDRAFT DAMPER  RC = ROOF CURB  CC = CURB CAP  BS = BIRD SCREEN  PP = PROVIDE WITH POLY-PRO COATING  VI = VIBRATION ISOLATORS									O OPERATE	UP TO 15 I	MINUTES AFTI	ER LIGHTS ARE TU	RNED OFF			


	LOUVER SCHEDULE										
MARK	NOMINAL SIZE	MIN FREE AREA	(CFM)	ТҮРЕ	MAKE	MODEL	NOTES				
L1	18"x24"	1.1	440	OUTSIDE AIR LOUVER	GREENHECK	ESD-635	1, 2, 3, 4, 5, 6				
L2	32"x8"	2.2	880	EXHAUST AIR LOUVER	GREENHECK	ESD-635	1, 2, 3, 4, 5, 6				

- NOTES:

  1. COORDINATE EXACT LOCATION AND MOUNTING OF LOUVER WITH ARCHITECTURAL ELEVATION.
- 2. COORDINATE COLOR AND FINISH WITH ARCHITECT.
- 3. AIRFLOW QUANTITIES AS NOTED ON MECHANICAL DRAWINGS.
- 4. PROVIDE WITH POLY-PRO COATING.
- 5. COORDINATE EXACT LOUVER WIDTH/HEIGHT WITH ACTUAL WALL CMU CONSTRUCTION. 6. PROVIDE GRAVITY BACKDRAFT DAMPER AND 1/4" GALVANIZED BIRDSCREEN MESH.



2 GAS FLUE THRU ROOF DETAIL N.T.S.



✓ INLINE EXHAUST FAN DETAIL

OF ALL DED 18	

ENGIN KGS PRO

SCHI

MECHANICAL

WDED 18									
NOTES	NAME	DATE							
SURVEY BY									
DRAWN BY									
DESIGNED BY									
CHECKED BY									



M-4-01

REVIEWED BY

2	EF-1 SEQUENCE OF OPERATIONS
J	N.T.S.

CEILING MOUNTED CONSTANT VOLUME EXHAUST FAN.

1. THE EXHAUST FAN SHALL RUN CONTINUOUSLY AND ONLY DEACTIVATED BY THE DISCONNECT SWITCH FOR MAINTENANCE AND REPAIR.

SEQUENCE OF OPERATION

EXHAUST FAN CONTROL - EF-1

FAN MOTOR - ON/OFF CONTROL:

SYSTEM DESCRIPTION

#### PLUMBING ABBREVIATIONS EYE WASH FIRE DEPARTMENT CONNECTION A(AMP) FIRE PROTECTION AMPERE ABOVE FINISHED FLOOR AFF FINISH(ED) FIN.('D) **ADJUSTABLE** ADJ. FINISH FLOOR AIR CONDITIONING FIXTURE FIXT. FIXTURE UNIT AIR HANDLER UNIT APPROX. FLEXIBLE APPROXIMATE(LY) ARCH('L) FLOOR ARCHITECT(URAL) FLOOR CLEAN OUT BUILDING BLDG FLOOR DRAIN BRITISH THERMAL UNI BTU FLOOR SINK CAST IRON FLUSH VALVE CENTER FOOT/FEET CLEAN OUT FROM FLOOR ABOVE COLD WATER FROM FLOOR BELOW CONCRETE CONC. GALLONS PER FLUSH CONCRETE MASONRY UNIT CMU GALLONS PER MINUTE GPM CONDENSATE DRAIN COND GALV. CONDENSING UNIT GALVANIZED CU GAS HEATER CONSTRUCTION CONST. CORRIDOR CORR. **GAS PIPING** GAS PRESSURE REGULATOR GPR CUBIC FOOT PER HOUR CFH DEGREE FAHRENHEIT DegF. GENERAL CONTRACTOR DEMOLISH(ITION) DEMO GREASE WASTE DETAIL GROUND GND. DIAMETER DIA./Ø GROUND CLEANOUT GCO DISCONNECT GYPSUM BOARD GYP. DISHWASHER BOX HTR HEATER DIVISION HEAT PUMP UNIT/HORSEPOWER DOMESTIC COLD WATER **HEATING, VENTILATION & AIR** HVAC DOMESTIC HOT WATER DHW CONDITIONING DOMESTIC HOT WATER RECIRCULATION DHWR HOSE BIBB DOUBLE HOT WATER DOUBLE CLEAN OUT HOT WATER RETURN INFORMATION INFO DOWNSPOUT BOOT INLET DOWNSPOUT NOZZLE DSN INSPECTION PORTAL DRAINAGE FIXTURE UNIT DFU INSULATION INSUL. \_DWG(S) DRAWING(S) INVERT INV. EACH **JANITOR EFFICIENCY** LAVATORY ELECTRIC(AL) LONG RADĪŪS ELBOW ELECTRIC WATER COOLER MAN HOLE **ELEVATION** ELEV. MFR. MANUFACTURE(R) **ELEVATOR SUMP PUMP WASTE** MAXIMUM MAX EMERGENCY EYE WASH MAXIMUM OVERCURRENT \_MOCP EMERGENCY EYE WASH & SHOWER EEW/S PROTECTION EMERGENCY MIXING VALVE EMV MECH **MECHANICAL** EMERGENCY SHOWER \_ MPG MEDIUM PRESSURE GAS ENGINEER ENGR. MEZZ MEZZANINE EQUAL EQ. MINIMUM MIN EQUIPMENT EQPT. MINIMUM CURRENT AMPACITY MCA ETCETERA MISCELLANEOUS MISC. EXHAUST FAN MOP SINK EXISTING EXIST. MULTIPLE MULT. EXTERIOR CLEANOUT NOT APPLICABLE EXPOSED NOTE: NOT ALL ABBREVIATIONS ON THIS LIST ARE APPLICABLE TO THIS PROJECT.

NATURAL	NAT.
NATURAL GAS	NG
NOMINAL	NOM.
NON-FREEZE WALL HYDRANT	NWH
NORTH	N
NOT IN CONTRACT	N.I.C.
NOT TO SCALE	N.T.S.
NUMBER	NO./#
OUTSIDE AIR	OA
OUTLET	OUT.
OVERFLOW ROOF DRAIN	ORD
OVERFLOW STORM DRAIN	OSD
PANEL	PNL.
PARTIAL	PART.
PHASE	 PH./Ø
POINT OF CONNECTION	POC
POLYVINYL CHLORIDE	PVC
POUND(S)	LBS
POUNDS PER SQUARE INCH	PSI
QUANTITY	OTY.
RADIUS	RAD
REFRIGERATOR BOX	RB
RECESSED	REC.
REINFORCE(ING)(ED)(MENT)	REINF.
RETURN AIR	
	RA
REQUIRE(D)	REQ.('[
ROOF DRAIN	RD
ROOF TOP UNIT	RTU
ROOM	RM
SANITARY SEWER	SS
SCHEDULE	SCH
SECTION	SECT.
SHOWER	SH
SOUTH	S
SPECIFICATION(S)	SPEC(S
SPRINKLER	SPRINK
SQUARE	SQ.
SQUARE FEET	SF
STAINLESS STEEL	SST
STEEL	STL.
STORM DRAIN	SD
SUPPLY FIXTURE UNIT	SFU
TEMPORARY	TEMP.
TEXAS	TX
THROUGH	THRU.
TOTAL DEVELOPED LENGTH	TDL
TO FLOOR ABOVE	TFA
TO FLOOR BELOW	TFB
TOP OF STEEL	TOS
TRENCH DRAIN	TD
TYPICAL	TYP.
JNDERGROUND	UG
UNDERWRITER LABORATORIES	UL
INC.	
UNIT HEATER	UH
ONIT REATER	
UNLESS NOTED OTHERWISE	U.N.O.

# PLAN/DETAIL DESIGNATION

PLAN NAME/DETAIL TITLE VIEW NUMBER

**PLUMBING LINE TYPES PLUMBING RISER SYMBOLS** ----- • COLD WATER PIPING ----- • HOT WATER PIPING RISER COLD WATER GENERAL ---- • HOT WATER RETURN PIPING ---- • WASTE WATER PIPING • VENT PIPING RISER COLD/HOT WATER -----G----- • GAS PIPING LAVATORY • FIRE PIPING — — — • STORM PIPING RISER COLD WATER HOSE BIBB PLUMBING DEMOLITION LINE TYPES RISER WASTE WATER GENERAL ---- • DEMOLITION COLD WATER PIPING ---- • DEMOLITION HOT WATER PIPING ---- • DEMOLITION WASTE WATER PIPING RISER WASTE WATER LAVATORY ---- • DEMOLITION GAS PIPING ---- • DEMOLITION FIRE PIPING ---- • DEMOLITION STORM PIPING RISER WASTE WATER FLOOR DRAIN PLUMBING EXISTING LINE TYPES RISER WASTE WATER FLOOR SINK ----- • EXISTING COLD WATER PIPING ---- • EXISTING HOT WATER PIPING ---- • EXISTING WASTE WATER PIPING RISER WASTE WATER HUB DRAIN — — — — • EXISTING VENT PIPING -----G------ • EXISTING GAS PIPING RISER WASTE WATER VENT THROUGH ROOF

EXISTING FIRE PIPING

— — — — • EXISTING STORM PIPING

# PLUMBING SYMBOLS

 POINT OF CONNECTION FLOOR CLEAN OUT - SEE SCHEDULE DOUBLE EXTERIOR CLEAN OUT **DCO** ⊢ CO CLEAN OUT WALL CLEAN OUT FLOOR DRAIN WATER HAMMER ARRESTER HOSE BIBB NON-FREEZE WALL HYDRANT FLOOR SINK

URINAL

UTILITY

VOLUME

WEIGHT

WITHOUT

WITH

VENT THROUGH ROOF

WATER HAMMER ARRESTOR

WALL CLEANOUT

**WASTE WATER** 

WATER CLOSET

WATER HEATER

VENT

BALL VALVE

CHECK VALVE

 FLOW CONTROL VALVE GAS COCK

GAS REGULATOR

 GATE VALVE OS&Y GATE VALVE

 STRAINER INSPECTION PORTAL

PIPING UP

 PIPING DOWN PIPING TEE DOWN

BACKFLOW PREVENTER

PLUMBING GENERAL NOTES

WCO

WHA

W/O

WH

\_ww

A. DO NOT SCALE DRAWINGS. REFER TO ARCHITECTURAL DOCUMENTS FOR EXACT LOCATION OF FIXTURES & EQUIPMENT

B. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE PLUMBING SYSTEMS AS INDICATED ON THE DRAWINGS, AND AS SPECIFIED AND REQUIRED BY CODE.

C. ELEVATIONS AS SHOWN ON THE DRAWINGS ARE TO THE BOTTOM OF ALL PRESSURE PIPING AND TO THE INVERT OF ALL GRAVITY PIPING.

D. MAINTAIN A MINIMUM OF 2 FEET OF GROUND COVER OVER ALL UNDERGROUND WATER MAINS AND UNDERGROUND SEWERS AND DRAINS.

E. PROVIDE SHUTOFF VALVES IN ALL DOMESTIC WATER PIPING SYSTEM BRANCHES.

F. UNLESS OTHERWISE NOTED, ALL DOMESTIC COLD WATER PIPING SHALL BE A MINIMUM

G. UNLESS OTHERWISE NOTED, ALL PIPING IS OVERHEAD, TIGHT TO THE UNDERSIDE OF THE SLAB, WITH SPACE FOR INSULATION IF REQUIRED.

H. INSTALL PIPING SO ALL VALVES, STRAINERS, UNIONS, TRAPS, FLANGES, AND OTHER APPURTENANCES REQUIRING ACCESS ARE ACCESSIBLE

INSTALL ALL PIPING WITHOUT FORCING OR SPRINGING.

J. ALL PIPING SHALL CLEAR DOORS AND WINDOWS.

K. ALL PIPING SHALL GRADE TO LOW POINTS. PROVIDE HOSE END DRAIN VALVES AT THE BOTTOM OF ALL RISERS AND LOW POINTS

L. UNIONS AND/OR FLANGES SHALL BE INSTALLED AT EACH PIECE OF EQUIPMENT, IN BYPASSES, AND IN LONG PIPING RUNS (100 FT. OR MORE) TO PERMIT DISASSEMBLY FOR ALTERATION AND REPAIRS.

M. ALL VALVES SHALL BE ADJUSTED FOR SMOOTH AND EASY OPERATION.

N. ALL VALVES AND STRAINERS SHALL BE THE FULL SIZE OF THE PIPE BEFORE REDUCING THE SIZE TO MAKE CONNECTIONS TO THE EQUIPMENT.

O. PROVIDE ALL PLUMBING FIXTURES AND EQUIPMENT WITH ACCESSIBLE STOPS.

P. ALL BALANCING VALVES AND BUTTERFLY VALVES SHALL BE PROVIDED WITH POSITION INDICATORS AND MAXIMUM ADJUSTABLE STOPS (MEMORY STOPS).

Q. ALL VALVES SHALL BE INSTALLED SO THE VALVE REMAINS IN SERVICE WHEN THE EQUIPMENT OR PIPING ON THE EQUIPMENT SIDE OF THE VALVE IS REMOVED.

R. ALL PIPING WORK SHALL BE COORDINATED WITH ALL TRADES INVOLVED PRIOR TO INSTALLATION. OFFSETS IN PIPING AROUND OBSTRUCTIONS SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

S. PROVIDE FLEXIBLE CONNECTIONS IN ALL PIPING SYSTEMS CONNECTED TO PUMPS AND OTHER EQUIPMENT THAT REQUIRE VIBRATION ISOLATION. FLEXIBLE CONNECTIONS SHALL BE PROVIDED AS CLOSE TO THE EQUIPMENT AS POSSIBLE OR AS INDICATED ON THE DRAWINGS.


T. PROVIDE BACKFLOW PREVENTERS AT ALL LOCATIONS REQUIRED BY THE LATEST ADOPTED CODES AND ORDINANCES.

U. PROVIDE HEAT TRACE FOR EXPOSED PIPING AT 3 WATTS / FT.

KGS PRO

Ŋ

LUM LUM



NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		
REVIEWED BY		



UPC 2015 CITY OF AUSTIN **AMMENDMENTS** 


APPLICABLE CODES

PLUMBING GENERAL NOTES P-1-01 PLUMBING PLAN - DEMOLITION PLUMBING PLAN - NEW WORK P-1-02 PLUMBING SCHEDULES, P-3-01 CALCULATIONS, AND DETAILS

PLUMBING RISERS P-6-02 PLUMBING RISERS

P-0-00

NOTE: NOT ALL SYMBOLS ON THIS LIST ARE APPLICABLE TO THIS PROJECT.



# **DEMOLITION NOTES**

-> KEYED NOTES

RECLAMATION SYSTEM.

FIELD-VERIFY SIZE AND CAPACITY.

CONNECTIONS TO REMAIN.

- A. REFER TO GENERAL NOTES ON SHEET P-0-00 FOR ADDITIONAL INFORMATION.
- B. EXISTING CONDITIONS ARE BASED ON EXISTING DRAWINGS AND SHALL BE FIELD-VERIFIED BY CONTRACTOR.
- C. PIPING SHOWN ON PLANS THAT IS NOT ANNOTATED IS EXISTING TO REMAIN AND SHALL BE PROTECTED FROM DAMAGE DURING DEMOLITION AND NEW WORK.

REMOVE EXISTING WATER RECLAMATION SYSTEM, TRUCK-WASHING EQUIPMENT, AND ASSOCIATED PLUMBING CONNECTIONS. EXISTING WATER RECLAMATION SYSTEM SHALL BE REMOVED WITH EXTREME CAUTION. W.E.T. REPRESENTATIVE

SHALL BE PRESENT AT REMOVAL TO SECURE CONNECTIONS FOR FUTURE

REMOVE EXISTING WATER HEATER AND ASSOCIATED VALVES, PIPING, AND

3. EXISTING INCOMING 3"CW LINE TO REMAIN. CONTRACTOR TO FIELD-VERIFY SIZE.

5. REMOVE EXISTING FITTING. REFER TO NEW WORK FOR REPLACEMENT FITTING.

5. EXISTING SAND/OIL INTERCEPTOR AND ASSOCIATED PLUMBING PIPING AND

7. ALL EXISTING DRAINS IN EQUIPMENT ROOM TO REMAIN.

REMOVE INCOMING 1-1/4" LOW PRESSURE GAS LINE BACK TO REGULATOR. EXISTING MEDIUM PRESSURE 2" GAS LINE AND REGULATOR TO REMAIN. CONTRACTOR TO

ENCOTECH

**EMOLITION** 


PLUMBING

	ED	
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		
REVIEWED BY		



PLUMBING PLAN - DEMOLITION

SCALE: 1/8"=1'-0"



PLUMBING PLAN - NEW WORK

SCALE: 1/8"=1'-0"



# NOTES

- A. REFER TO GENERAL NOTES ON SHEET P-0-00 FOR ADDITIONAL INFORMATION.
- B. PROVIDE HEAT TRACE AT 3 W/FT FOR PIPING TO FAR BAY.
- C. PIPING AND CONDUIT TO FAR BAY SHALL BE ROUTED THROUGH WALL AND OVER ROOF SO AS NOT OBSTRUCT WASH EQUIPMENT.
- D. PROVIDE ACCESSIBLE VALVES WHERE VALVE SYMBOL IS INDICATED.
- EXISTING CONDITIONS ARE BASED ON EXISTING DRAWINGS AND SHALL BE FIELD-VERIFIED BY CONTRACTOR.
- PIPING SHOWN ON PLANS THAT IS NOT ANNOTATED IS EXISTING TO REMAIN AND SHALL BE PROTECTED FROM DAMAGE DURING DEMOLITION AND NEW WORK.
- G. PROVIDE ISOLATION VALVES AT ALL EQUIPMENT.
- H. REFER TO PLUMBING RISER FOR ALL VALVES, PIPING, AND ACCESSORIES.
- ALL EXISTING ABOVE GRADE TRUCK WASH PIPING AND EQUIPMENT IN THE BAY SHALL BE REMOVED. REPAIR AND PATCH PER ARCHITECTURAL REQUIREMENTS.

#### KEYED NOTES

- PROVIDE NEW 120 GPM WATER RECLAMATION SYSTEM, TO BE SERVED BY NEW 2"NON-POTABLE WATER (NPW) MAKE-UP LINE AND DRAINAGE CONNECTIONS TO EXISTING DRAINAGE SYSTEM. COORDINATE WITH W.E.T. REPRESENTATIVE.
- PROVIDE NEW 25 GPM, 500 PSI HIGH PRESSURE CLEANING WATER BLASTER. SUPPLY NEW 3/4"CW SCHEDULE 40 GALVANIZED PIPE. COORDINATE WITH W.E.T. REPRESENTATIVE.
- PROVIDE NEW 4 GPM, 400,000 CFH, 3,000 PSI AALADIN PRESSURE WASHER. COORDINATE WITH W.E.T. REPRESENTATIVE.
- . PROVIDE WALL MOUNT BOOM AND ASSEMBLY SERVING PRESSURE WASHER. SUPPLY 3"PVC CONDUIT FROM AALADIN PRESSURE WASHER EQUIPMENT TO BOOM.
- 5. EXISTING INCOMING 3"CW LINE TO REMAIN. CONTRACTOR TO FIELD-VERIFY SIZE.
- PROVIDE NEW 2" LOW PRESSURE GAS LINE FROM EXISTING TO REMAIN REGULATOR. TOTAL LOAD OF 900 CFH. TOTAL DEVELOPED LENGTH OF 80 FEET.
- 7. REPLACE EXISTING FITTING WITH WYE FITTING.
- B. EXISTING SAND/OIL INTERCEPTOR AND ASSOCIATED PLUMBING PIPING AND CONNECTIONS TO REMAIN.
- 9. ALL EXISTING DRAINS IN EQUIPMENT ROOM TO REMAIN.
- 10. REPLACE EXISTING WATER SOFTENER AND AIR COMPRESSOR. COORDINATE WITH W.E.T. REPRESENTATIVE.
- 11. EXISTING 3/4"CW CONNECTION TO WALL HYDRANT TO REMAIN.
- 12. EMERGENCY EYE WASH / SHOWER AND ASSOCIATED PLUMBING FIXTURE CONNECTIONS TO REMAIN.
- 13. EXISTING TRAP PRIMER TO REMAIN.
- 14. PROVIDE WATER BLASTER. SUPPLY 3/4"PVC CONDUIT FROM HIGH PRESSURE EQUIPMENT TO BLASTER.
- 15. 1" MAKEUP WATER TO TANK FILL.

REVISION DESCRIPTION	ISSUE FOR PERMIT					
DATE	11/27/2020					
ВҮ						
ZEV NO						

FNCOTICH



WORK

ENGIN KGS

MBIN

PLUN

	) le lu	
NOTES	NAME	DATE
SURVEY BY		
DRAWN BY		
DESIGNED BY		
CHECKED BY		
REVIEWED BY		




P-1-02


- 1. THE MINIMUM WIDTH OF THE TRENCH SHOULD BE THE PIPE OD (OUTSIDE DIAMETER) PLUS 16 INCHES OR THE PIPE OUTSIDE DIAMETER TIMES 1.25 PLUS 12 INCHES. THE SPACE BETWEEN THE PIPE AND TRENCH WALL MUST BE WIDER THAN THE COMPACTION EQUIPMENT USED TO COMPACT THE BACKFILL.
- 2. PROVIDE A MINIMUM OF 4 INCHES OF FIRM, STABLE AND UNIFORM BEDDING MATERIAL IN THE TRENCH BOTTOM. IF ROCK OR UNYIELDING MATERIAL IS ENCOUNTERED, A MINIMUM OF 6 INCHES OF BEDDING SHALL BE USED. BLOCKING SHOULD NOT BE USED TO CHANGE PIPE GRADE OR TO INTERMITTENTLY SUPPORT PIPE OVER LOW SECTIONS IN THE TRENCH.
- 3. THE PIPE SHOULD BE SURROUNDED WITH AN AGGREGATE MATERIAL WHICH CAN BE EASILY WORKED AROUND THE SIDES OF THE PIPE. BACKFILLING SHOULD BE PERFORMED IN LAYERS OF 6 INCHES WITH EACH LAYER BEING SUFFICIENTLY COMPACTED TO 85% TO 95%
- 4. A MECHANICAL TAMPER IS RECOMMENDED FOR COMPACTING SAND AND GRAVEL. THESE MATERIALS CONTAIN FINE-GRAINS, SUCH AS SILT AND CLAY. IF A TAMPER IS NOT AVAILABLE, COMPACTING SHOULD BE DONE BY HAND.
- 5. THE TRENCH SHOULD BE COMPLETELY FILLED. THE BACKFILL SHOULD BE PLACED AND SPREAD IN UNIFORM LAYERS TO PREVENT ANY UNFILLED SPACES OR VOIDS. LARGE ROCKS, STONES, FROZEN CLODS, OR OTHER LARGE DEBRIS SHOULD BE REMOVED. STONE BACKFILL SHALL PASS THROUGH A 1-1/2" SIEVE. ROCK SIZE SHOULD BE ABOUT ONE-TENTH OF THE PIPE OUTSIDE DIAMETER. HEAVY TAMPERS OR ROLLING EQUIPMENT SHOULD ONLY BE USED TO CONSOLIDATE THE FINAL BACKFILL.
- 6. TO PREVENT DAMAGE TO THE PIPE AND DISTURBANCE TO PIPE EMBEDMENT, A MINIMUM DEPTH OF BACKFILL ABOVE THE PIPE SHOULD BE MAINTAINED. PIPE SHOULD ALWAYS BE INSTALLED BELOW THE FROST LEVEL. TYPICALLY, IT IS NOT ADVISABLE TO ALLOW VEHICULAR TRAFFIC OR HEAVY CONSTRUCTION EQUIPMENT TO TRAVERSE THE PIPE TRENCH.
- 7. INSTALL PIPING IN ACCORDANCE WITH ASTM D2321 FOR UNDERGROUND GRAVITY SYSTEMS AND ASTM D2774 FOR UNDERGROUND PRESSURE PIPING.

# $\frac{\textbf{4}}{\textbf{N.T.S.}} \frac{\textbf{UNDERGROUND INSTALLATION OF PLASTIC PIPE}}{\textbf{N.T.S.}}$

- 1. ATTACH SUPPORTS FOR ALL PIPING SUSPENDED FROM THE STEEL STRUCTURE TO THE TOP CHORD
- 2. PROVIDE COPPER OR PLASTIC COATED HANGERS FOR NON-INSULATED COPPER PIPE.








MANUAL BAY (MAX FLOW 33 GPM)	1 x	44.0 F.U.=	44.0
4" FLOOR DRAIN/FLOOR SINK	4 x	8.0 F.U.=	32.0
AUTOMATIC BAY	1 x	8.0 F.U. =	8.0
TOTAL FIXTURE UNITS		·=	— 84.0

	WATER CALCULA	TION		
EMERGENCY EYE	WASH / SHOWER	1 x	23.0 GPM =	23.0 GPM
TRUCK WASH EQI	JIPMENT	1 x	74.0 GPM =	74.0 GPM
FIRST HOSE BIBB		1 x	2.5 F.U. =	2.5 F.U.
ADDITIONAL HOS	SE BIBBS	2 x	1.0 F.U. =	2.0 F.U.
4.5 FIXTURE UNIT	S		=	9.0 GPM
TOTAL GPM			=	106.0 GPN
HIGHEST FIXTURE (10 FT.) x 0.43 = 4	= 10 FEET .3 PSI STATIC LOSS			
HORIZONTAL PIP	E LENGTH TAP TO METER (FIELD-VE	RIFY)	=	10 FEET
HORIZONTAL PIP	E LENGTH METER TO BUILDING (FIEI	LD-VERIFY)	=	50 FEET
HORIZONTAL PIP	E LENGTH BUILDING TO LAST FIXTUI	RE	=	85 FEET
VERTICAL PIPE LE	NGTH BUILDING RISE TO HIGHEST F	IXTURE	=	10 FEET
	TH TITTING LOSS) = 194 FEET TOTAL DEV			155 FEET
		/ELOPED LE PS =	i Loss 9.8 psi	155 FEET
(155 FT.) x 1.25 (F	DEVICE  METER (FIELD-VERIFY)	/ELOPED LE PS = =	I LOSS 9.8 PSI 4.3 PSI	155 FEET
(155 FT.) x 1.25 (F SIZE	DEVICE  METER (FIELD-VERIFY) STATIC	/ELOPED LE PS = = =	I LOSS 9.8 PSI 4.3 PSI 12.0 PSI	155 FEET
(155 FT.) x 1.25 (F SIZE 2"	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER	/ELOPED LE PS = = =	NGTH I LOSS 9.8 PSI 4.3 PSI 12.0 PSI 30.0 PSI	155 FEET
(155 FT.) x 1.25 (F SIZE 2" TOTAL PRESSURE AT STR	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER  EQUIPMENT  BUILDING LOSS	PS==	ENGTH  I LOSS  9.8 PSI  4.3 PSI  12.0 PSI  30.0 PSI  56.1 PSI	155 FEET
(155 FT.) x 1.25 (F SIZE 2" TOTAL PRESSURE AT STR BUILDING LOSS	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER  EQUIPMENT  BUILDING LOSS	PS===	9.8 PSI 4.3 PSI 12.0 PSI 30.0 PSI 56.1 PSI	
(155 FT.) x 1.25 (F SIZE 2" TOTAL PRESSURE AT STR BUILDING LOSS DIFFERENCE	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER  EQUIPMENT  BUILDING LOSS	PS=	9.8 PSI 4.3 PSI 12.0 PSI 30.0 PSI 56.1 PSI	65.0 PSI
(155 FT.) x 1.25 (F SIZE 2" TOTAL PRESSURE AT STR BUILDING LOSS	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER  EQUIPMENT  BUILDING LOSS  EET (FIELD-VERIFY)	PS==== WABLE	9.8 PSI 4.3 PSI 12.0 PSI 30.0 PSI 56.1 PSI	65.0 PSI 56.1 PSI
(155 FT.) x 1.25 (F SIZE 2" TOTAL PRESSURE AT STR BUILDING LOSS DIFFERENCE	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER  EQUIPMENT  BUILDING LOSS	PS==== WABLE	9.8 PSI 4.3 PSI 12.0 PSI 30.0 PSI 56.1 PSI	65.0 PSI 56.1 PSI
(155 FT.) x 1.25 (F SIZE 2" TOTAL PRESSURE AT STR BUILDING LOSS DIFFERENCE (8.9 / 194) x 100 =	DEVICE  METER (FIELD-VERIFY)  STATIC  BACKFLOW PREVENTER  EQUIPMENT  BUILDING LOSS  EET (FIELD-VERIFY)	PS==== WABLE GTH	I LOSS  9.8 PSI  4.3 PSI  12.0 PSI  30.0 PSI  56.1 PSI	65.0 PSI 56.1 PSI


\* VERIFY PRESSURE AT TIME OF CONSTRUCTION. IF GREATER THAN 65 PSI

PROVIDE AND INSTALL PRESSURE REDUCING VALVE TO REDUCE WATER


PRESSURE TO 65 PSI MAXIMUM.



2 VERTICAL PIPING SUPPORT (CONCRETE WALL)
N.T.S.



TYPICAL LOW PRESSURE GAS EQUIPMENT CONNECTION



ENCOTECH

**CALCULATIONS**,

SCHED

NAME DATE SURVEY BY DRAWN BY DESIGNED BY CHECKED BY REVIEWED BY




P-3-01

# NOTES


- A. REFER TO GENERAL NOTES ON SHEET P-0-00 FOR ADDITIONAL INFORMATION.
- B. RISERS ARE DRAWN SCHEMATICALLY AND INTENDED TO CLARIFY SIZES OF PIPING. REFER TO PLANS FOR ROUTING OF PIPING.
- C. EXISTING CONDITIONS ARE BASED ON EXISTING DRAWINGS AND SHALL BE FIELD-VERIFIED BY CONTRACTOR.

# KEYED NOTES

L. EXISTING TRAP PRIMER TO REMAIN.



PLUMBING DOMESTIC WATER RISER
N.T.S.



ENGINEERING CONSULTANTS


8500 Bluffstone Cove, Suite B-103
Austin, Texas 78759 | 512.338.1101
Project No.: 20049.MS.AUS



CITY OF AUSTIN, TX
DEPARTMENT OF PUBLIC WORKS
ENGINEERING SERVICES DEPARTMENT
KGSC TRUCK WASH FACILITY
PROPOSED IMPROVEMENTS

RISERS

PLUMBING



NDED L				
NOTES	NAME	DATE		
SURVEY BY				
DRAWN BY				
DESIGNED BY				
CHECKED BY				
REVIEWED BY				




P-6-01

# NOTES

- A. REFER TO GENERAL NOTES ON SHEET P-0-00 FOR ADDITIONAL INFORMATION.
- B. RISERS ARE DRAWN SCHEMATICALLY AND INTENDED TO CLARIFY SIZES OF PIPING. REFER TO PLANS FOR ROUTING OF PIPING.
- EXISTING CONDITIONS ARE BASED ON EXISTING DRAWINGS AND SHALL BE FIELD-VERIFIED BY CONTRACTOR.

# ← KEYED NOTES

CONNECT NEW 2" LOW PRESSURE (LESS THAN 2 PSI) NATURAL GAS PIPING TO EXISTING METER. TOTAL LOAD OF 900 CFH. TOTAL DEVELOPED LENGTH OF 80 FEET.



ENCOPERING CONSULTANTS



CITY OF AUSTIN, TX
DEPARTMENT OF PUBLIC WORKS
ENGINEERING SERVICES DEPARTMENT
KGSC TRUCK WASH FACILITY
PROPOSED IMPROVEMENTS

PLUMBING RISERS

NOTES	NAME	DATE		
SURVEY BY				
DRAWN BY				
DESIGNED BY				
CHECKED BY				
REVIEWED BY				



P-6-02

PLUMBING NATURAL GAS RISER
N.T.S.

#### **GENERAL NOTES**

- 1. THESE GENERAL NOTES SHALL APPLY UNLESS OTHERWISE SPECIFICALLY NOTED ON PLANS AND DETAILS.
- 2. CONSTRUCTION WORKMANSHIP, AND MATERIALS SHALL COMPLY WITH THE 2015 INTERNATIONAL BUILDING CODE (IBC).
- 3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND SHALL COORDINATE ALL STRUCTURAL PLANS AND DETAILS WITH ARCHITECTURAL, MECHANICAL, ELECTRICAL AND CIVIL DRAWINGS BEFORE STARTING WORK. IN CASE OF DISCREPANCY, THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF SAME IN A TIMELY
- 4. COMPLETE SHOP DRAWINGS FOR THE STRUCTURAL WORK SHALL BE SUBMITTED FOR REVIEW PRIOR TO COMMENCEMENT OF CONSTRUCTION IN ACCORDANCE WITH THE SPECIFICATIONS. REVIEW OF SHOP DRAWINGS BY THE ARCHITECT/ENGINEER DOES NOT RELIEVE THE CONTRACTOR OF FULL RESPONSIBILITY FOR CORRECT FABRICATION AND CONSTRUCTION OF THE WORK.
- 5. THE STRUCTURAL DRAWINGS SHALL NOT BE SCALED FOR DETERMINATION OF QUANTITIES, LENGTHS, OR FIT OF MATERIALS.
- 6. PRINCIPAL OPENINGS ARE SHOWN ON THE STRUCTURAL DRAWINGS, THE CONTRACTOR SHALL REFER TO ARCHITECTURAL, MECHANICAL, ELECTRICAL, HVAC AND PLUMBING DRAWINGS FOR SLEEVES, CURBS, INSERTS AND SIMILAR DETAILS NOT SHOWN. SIZE AND LOCATION OF ALL OPENINGS SHALL BE VERIFIED BY THE CONTRACTOR. ANY DEVIATION FROM OPENINGS SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE BROUGHT TO THE ARCHITECT/ENGINEERS ATTENTION PRIOR TO CONSTRUCTION.
- 7. THE STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHODS OF CONSTRUCTION UNLESS SO STATED OR NOTED. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE WORKERS AND ALL OTHER PERSONS DURING CONSTRUCTION.
- 8. THE CONTRACTOR SHALL PROVIDE TEMPORARY ERECTION BRACING AND SHORING OF ALL STRUCTURAL WORK AS REQUIRED FOR STABILITY OF THE STRUCTURE DURING ALL PHASES OF CONSTRUCTION. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE CONSTRUCTION MANAGER OF ANY CONDITION WHICH, IN HIS OPINION, MIGHT ENDANGER THE STABILITY OF THE STRUCTURE OR CAUSE DISTRESS IN THE STRUCTURE.
- 9. CONSTRUCTION MATERIALS SHALL NOT BE STORED ON FLOORS OR ROOFS IN EXCESS OF THE DESIGN LIVE LOADS. IMPACT SHALL BE AVOIDED WHEN PLACING MATE

#### SUBGRADE PREPARATION

1. AFTER EXISTING SUBGRADE HAS BEEN EXCAVATED TO FACILITATE THE CONSTRUCTION OF TRENCH AND PIT, BACKFILL TRENCH WITH NORMAL SET CONTROLLED LOW STRENGTH MATERIAL PER COA SPEC ITEM 402S AS NEEDED PRIOR TO CONSTRUCTION OF REINFORCED TRENCH, PIT AND SLAB. SEE DRAWINGS FOR CONCRETE AND WATERSTOP DETAILS.

#### SLAB-ON-GRADE NOTES

- 1. FLOOR SLAB SHALL BE PLACED OVER A 15 MIL VAPOR RETARDER. TAPE ALL SEAMS, PENETRATIONS AND TEARS IN THE VAPOR RETARDER WITH A COMPATIBLE WATERPROOF TAPE. SEE FLOOR PLAN FOR SLAB THICKNESS.
- 2. REINFORCE SLAB AS SHOWN ON FLOOR PLAN. REBARS SHALL BE PLACED AND SUPPORTED ON CHAIRS OR CONCRETE BRIQUETS, AT SLAB MID DEPTH.
- 3. PROVIDE THE FOLLOWING JOINTS TO ALIGN WITH EXISTING SLAB JOINTS:
- B. SAW CUT CONTROL JOINTS ELSEWHERE 1" DEEP OR ONE QUARTER OF THE SLAB DEPTH DEEP, WHICHEVER IS GREATER.
- 4. CUT SAW CUT JOINTS WITHIN 8 HOURS OF POURING CONCRETE.
- 5. SLAB SURFACE FINISH SHALL MATCH THE EXISTING SLAB

#### VAPOR BARRIER NOTES

- 1. A VAPOR BARRIER SHALL BE PLACED UNDER THE CONCRETE SLAB. THE VAPOR BARRIER SHALL CONSIST OF A POLYETHYLENE OR POLYOLEFIN RESIN GEOMEMBRANE THAT MEETS THE FOLLOWING REQUIREMENTS:
- a. MEET OR EXCEED THE CLASS A REQUIREMENTS OF ASTM E1745
- b. WATER VAPOR TRANSMISSION RATE (WVTR) OF 0.006 GRAINS (0.012 PERMS) OR LESS PER SQUARE FOOT IN ACCORDANCE WITH ASTM E96
- c. MINIMUM PUNCTURE RESISTANCE OF 2445 GRAMS IN ACCORDANCE WITH ASTM D1709
- d. MINIMUM TENSILE STRENGTH OF 76.6 PLF/INCH IN ACCORDANCE WITH ASTM D882
- e. MINIMUM THICKNESS OF 15 MILS
- 2. ACCEPTABLE PRODUCT IS STEGO WRAP CLASS A VAPOR BARRIER BY STEGO INDUSTRIES LLC, SAN JUAN CAPISTRANO, CALIFORNIA, OR APPROVED EQUAL.
- 3. VAPOR BARRIER SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS. SPECIAL ATTENTION SHALL BE PAID TO THE VAPOR BARRIER INSTALLATION AT PIPE AND CONDUIT PENETRATIONS.
- 4. LAP JOINTS IN VAPOR BARRIER A MINIMUM OF 6 INCHES AND SEAL CONTINUOUSLY WITH A PRESSURE SENSITIVE. HIGH-DENSITY POLYETHYLENE TAPE MANUFACTURED SPECIFICALLY FOR THE USE OF SEALING VAPOR BARRIER LAPS. THE TAPE SHALL MEET THE FOLLOWING REQUIREMENTS:
- a. WATER VAPOR TRANSMISSION RATE (WVTR) OF 0.3 PERMS OR LESS PER SQUARE FOOT IN ACCORDANCE WITH ASTM E96
- b. MINIMUM TAPE WIDTH OF 4 INCHES
- 5. THE VAPOR BARRIER SHALL BE CONTINUOUS UNDER THE SLAB. THE VAPOR BARRIER SHALL BE INSTALLED SMOOTH AND LEVEL. BUNCHING WILL NOT BE PERMITTED AND SHALL BE CORRECTED PRIOR TO CONCRETE PLACEMENT
- 6. CAREFULLY INSPECT VAPOR BARRIER FOR DAMAGE, TEARS OR PENETRATIONS PRIOR TO CONCRETE PLACEMENT. ALL DAMAGED AREAS SHALL BE REPAIRED BY CUTTING PATCHES OF VAPOR BARRIER, OVERLAPPING DAMAGED AREA 6 INCHES AND TAPING ALL EDGES.

#### **CONCRETE NOTES**

- 1. ALL CONCRETE WORK SHALL CONFORM TO THE AMERICAN CONCRETE INSTITUTE (ACI) SPECIFICATION, ACI #301 & BUILDING CODE REQUIREMENTS, ACI #318, LATEST EDITION, FOR BUILDING STRUCTURES.
- 2. ALL DETAILING, FABRICATION AND ERECTION OF REINFORCING BARS, UNLESS OTHERWISE NOTED, MUST FOLLOW THE ACI "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE", ACI #315,
- 3. UNLESS SHOWN OTHERWISE IN THE SPECIFICATIONS, CONCRETE SHALL BE CLASS 'S' CONCRETE WITH 4000 PSI MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS. ALSO REFER TO SPECIFICATIONS FOR ADDITIONAL CONCRETE MIX DESIGN REQUIREMENTS.
- 4. REINFORCING BARS SHALL BE NEW BILLET STEEL CONFORMING TO ASTM A-615, GRADE 60.
- 5. STANDARD PROTECTIVE COVER OF REINFORCING BARS UNLESS OTHERWISE NOTED SHALL BE

WHERE CAST AGAINST DIRT OR FILL	3 IN
WHERE CAST AGAINST SEAL SLAB	2 IN
EXPOSED TO EARTH, WATER, OR WEATHER	2 IN
SLABS AND WALLS	2 IN
OTHER	2 IVI

6. CONCRETE SLUMPS SHALL BE AS FOLLOWS:

SLAB ON METAL DECK----- 4" MAX, 2" MIN ----- 7" MAX. 5" MIN CONCRETE CONTAINING HRWR----- 10" MAX ALL OTHER CONCRETE ----- 5" MAX, 2" MIN

- 7. ALL ACCESSORIES SHALL BE IN ACCORDANCE WITH THE ACI "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE", ACI #315, LATEST EDITION. ACCESSORIES FOR INTERIOR CONCRETE SURFACES EXPOSED TO VIEW SHALL HAVE PLASTIC COATED FEET. ACCESSORIES FOR CONCRETE SURFACES EXPOSED TO EARTH, WEATHER, WATER, OR HIGH HUMIDITY SHALL BE FABRICATED OF STAINLESS STEEL OR PLASTIC. PROVIDE BOLSTERS AT SUSPENDED SLABS, WALLS AND WIDE BEAMS. PROVIDE STANDEES AT ALL SLABS WITH TWO LAYERS OF REINFORCING. FOR SLAB-ON-GRADE REINFORCING, PROVIDE CHAIRS MANUFACTURED FROM HOT-DIPPED GALVANIZED STEEL, STAINLESS STEEL, PLASTIC, OR PRECAST CONCRETE BLOCKS OF EQUAL OR GREATER COMPRESSIVE STRENGTH AS THE CONCRETE BEING POURED.
- 8. MAINTAIN A MINIMUM OF ONE BAR DIAMETER (BUT NOT LESS THAN 1") BETWEEN ALL CONTINUOUS REINFORCING BARS ON ALL SLABS. MAINTAIN A MINIMUM OF 1-1/2" BETWEEN BARS IN COLUMNS, AND A MINIMUM OF 1-1/2 TIMES THE MAXIMUM COARSE AGGREGATE SIZE IN ALL CASES.
- 9. BARS SCHEDULED AND DETAILED "CONT" SHALL BE LAPPED ACCORDING TO STANDARD TENSION LAP LENGTHS TABLE UNLESS OTHERWISE NOTED. THE SPLICES SHALL OCCUR AT MIDSPAN FOR TOP BARS AND OVER THE SUPPORTS FOR BOTTOM BARS.
- 10. ANY PROPOSED PENETRATIONS NOT MEETING ALL OF THE BELOW CRITERIA SHALL NOT BE ALLOWED WITHOUT THE WRITTEN APPROVAL OF THE STRUCTURAL ENGINEER:
  - a. NO PENETRATIONS ARE TO BE LARGER THAN 2" (2 1/2 SLEEVE) IN DIAMETER FOR BEAMS LESS THAN 18" WIDE. NO PENETRATIONS ARE TO BE LARGER THAN 4" (5" SLEEVE) IN DIAMETER FOR BEAMS GREATER THAN 18" WIDE.
  - b. NO PENETRATIONS ARE TO BE CLOSER THAN 4" TO ANY EDGE OF BEAMS.
  - c. PENETRATIONS LARGER THAN 3/4" (1" SLEEVE) DIAMETER MUST BE IN THE MIDDLE THIRD OF THE BEAM SPAN.
  - d. ONLY ONE (1) VERTICAL PENETRATION MAY OCCUR ACROSS THE WIDTH OF A BEAM. MULTIPLE VERTICAL PENETRATIONS OCCURRING ALONG THE LENGTH OF A BEAM ARE TO BE SPACED A MINIMUM OF 6" ON CENTER AND HAVE AT LEAST ONE STIRRUP BETWEEN THEM.
  - e. ALL HORIZONTAL PENETRATIONS ARE TO BE IN THE MIDDLE THIRD OF THE BEAM OR JOIST DEPTH. MULTIPLE HORIZONTAL PENETRATIONS OCCURRING ALONG THE LENGTH OF A BEAM OR JOIST ARE TO BE SPACED A MINIMUM OF 6" ON CENTER AND HAVE AT LEAST ONE STIRRUP BETWEEN THEM.
- 11. SHOP DRAWINGS SHALL BE PREPARED FOR ALL REINFORCING STEEL AND SUBMITTED FOR REVIEW BY ENGINEER. ENGINEERING DRAWINGS SHALL NOT BE REPRODUCED AND USED AS SHOP DRAWINGS.
- 12. WELDING OF REINFORCING BARS SHALL NOT BE PERMITTED, UNLESS APPROVED BY ENGINEER.
- 13. DURING PLACEMENT OF CONCRETE, USE TREMIE OR OTHER MEANS TO LIMIT FREE FALL OF CONCRETE TO 5'-0".
- 14. VERTICAL REINFORCING, DOWEL, AND LAPS ARE OFFSET IN DETAILS FOR CLARITY. BARS SHOULD BE CONSIDERED TO BE IN THE SAME PLANE AT EXTERNAL FACE.
- 15. CONCRETE PLACED BY PUMPING SHALL MEET THE FOLLOWING REQUIREMENTS:
  - COARSE AGGREGATE (AGG) SHALL BE GRADED FROM A MAXIMUM OF 1 1/2". MAXIMUM ALLOWABLE INCREASE IN CEMENT FACTOR SHALL BE 1/2 SACK PER CUBIC YARD OVER

  - MAXIMUM WATER CEMENT RATIO WILL CONFORM TO REQUIREMENTS STATED IN THE PROJECT SPECIFICATIONS. IF MORE WORKABILITY IS REQUIRED, AN ADMIXTURE MAY BE USED.
  - MAXIMUM WEIGHT RATIO OF FINE AGGREGATES TO COARSE AGGREGATES (AGG) SHALL NOT
  - EXCEED 2/3. REFER TO ACI 301, LATEST EDITION, SECTION 800, FOR OTHER PUMPING REQUIREMENTS.
- 16. NO HORIZONTAL JOINTS WILL BE PERMITTED IN SLABS OR BEAMS UNLESS SPECIFICALLY SHOWN ON DRAWINGS. CONTRACTOR MUST SUBMIT VARIANCE IN CONSTRUCTION JOINT LOCATIONS FOR REVIEW BY
- 17. WELDED WIRE FABRIC (WWF) SHALL BE SUPPLIED IN FLAT SHEETS ONLY. NO ROLLS ARE PERMITTED.

IN NO CASE SHALL CONCRETE BE PUMPED THROUGH AN ALUMINUM TUBE

18. USE 3/4" CHAMFER ON ALL EXPOSED CONCRETE CORNERS.

#### TRENCH SAFETY

1. THE CONTRACTOR SHALL PROVIDE TRENCH SAFETY DESIGN DOCUMENTS PREPARED AND SEALED BY A QUALIFIED REGISTERED PROFESSIONAL ENGINEER AS REQUIRED BY ALL LOCAL AND STATE LAWS. SAID ENGINEER SHALL ALSO BE RESPONSIBLE FOR ON SITE OBSERVATIONS. THE TRENCH SAFETY DESIGN DOCUMENTS SHALL BE FILED WITH THE APPROPRIATE GOVERNMENT AGENCY. THE CONTRACTOR SHALL FURNISH A SEPARATE AND DISTINCT PRICE FOR TRENCH SAFETY SYSTEM THAT MEETS OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION STANDARDS.

NONO.

#### SHOP DRAWING REVIEW AND SUBMITTAL NOTES

#### 1. REFER TO PROJECT SPECIFICATIONS FOR SUBMITTAL REQUIREMENTS.

SHOP DRAWINGS AND SUBMITTALS WILL BE REVIEWED FOR THE LIMITED PURPOSE OF CHECKING FOR CONFORMANCE WITH INFORMATION GIVEN AND THE DESIGN CONCEPT EXPRESSED IN THE CONTRACT DOCUMENTS.

SUBMITTAL REVIEW WILL NOT BE CONDUCTED FOR THE PURPOSE OF DETERMINING THE ACCURACY AND COMPLETENESS OF OTHER DETAILED INFORMATION SUCH AS DIMENSIONS AND QUANTITIES, OR FOR SUBSTANTIATING INSTRUCTIONS FOR INSTALLATION OR PERFORMANCE OF EQUIPMENT OR SYSTEMS DESIGNED BY THE CONTRACTOR. ALL OF THIS REMAINS THE RESPONSIBILITY OF THE CONTRACTOR.

REVIEW SHALL NOT CONSTITUTE APPROVAL OF SAFETY PRECAUTIONS OR OF ANY CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES.

APPROVAL OF A SPECIFIC ITEM SHALL NOT INDICATE APPROVAL OF AN ASSEMBLY OF WHICH THE ITEM IS A

2. SHOP DRAWINGS AND/OR PRODUCT DATA FOR THE FOLLOWING ITEMS ARE TO BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR REVIEW AND APPROVAL:

#### A. REINFORCING STEEL

SHOP DRAWINGS ARE TO BE DISTRIBUTED ONLY FROM RETURNED SUBMITTALS BEARING AN INITIALED REVIEW STAMP AND WORK ON THESE ITEMS SHALL NOT PROCEED UNLESS THE STAMP CLEARLY INDICATES THE DRAWINGS ARE "APPROVED" OR "APPROVED AS NOTED."

3. SHOP DRAWINGS AND/OR PRODUCT DATA FOR THE FOLLOWING ITEMS ARE TO BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR REVIEW. THE ENGINEER'S REVIEW WILL BE LIMITED TO CONFORMANCE WITH DESIGN AND PERFORMANCE CRITERIA SPECIFIED IN THE CONSTRUCTION DOCUMENTS AND THE INTERFACE BETWEEN THESE ITEMS/SYSTEMS AND THE BUILDING STRUCTURE. THIS REVIEW WILL CHECK THE COMPATIBILITY OF LOADS AND POSITIONS OF LOADS IMPARTED ONTO THE BUILDING STRUCTURE, AND COMPATIBILITY OF CONNECTIONS WITH THE BUILDING STRUCTURE. THE MANUFACTURER/ SUPPLIER AND ITS SPECIALTY STRUCTURAL ENGINEER RESPONSIBLE FOR THE DESIGN OF THE ITEM/SYSTEM WILL RETAIN ALL RIGHTS AND RESPONSIBILITIES FOR THE DESIGN OF THE PRODUCT AND THE CONNECTIONS TO THE BUILDING

#### A. CONCRETE MIXES

NO WORK ON STRUCTURAL ELEMENTS SUPPORTING OR RELATED TO THESE ITEMS IS TO PROCEED UNLESS THE REVIEW STAMP CLEARLY INDICATES "REVIEWED" OR "REVIEWED, SEE COMMENTS" BY THE STRUCTURAL ENGINEER.

4. CONCRETE IS A PRE-ENGINEERED MATERIAL DESIGNED BY THE SUPPLIER TO MEET THE STRENGTH AND PERFORMANCE CRITERIA SPECIFIED IN THE CONTRACT DOCUMENTS. CONCRETE MIX DESIGNS SHALL BE IN CONFORMANCE WITH ACI 318-14, CHAPTER 5, AND SHALL BE SUBMITTED TO THE INDEPENDENT TESTING LAB WITH APPROPRIATE HISTORICAL TEST DATA AND ANALYSIS FOR REVIEW AND APPROVAL. SUBMIT MIX DESIGNS AND THE TESTING LAB REVIEW TO THE ARCHITECT/ENGINEER FOR REVIEW.

MANY VARIABLES, INCLUDING MIX COMPONENTS AND ENVIRONMENTAL CONDITIONS AFFECT THE QUALITY OF CONCRETE. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING VARIABLES AND REQUESTING MIX MODIFICATIONS AND SHALL BE SOLELY RESPONSIBLE FOR THE QUALITY OF CONCRETE DELIVERED AND PLACED ON THE SITE.

- 5. GENERAL CONTRACTOR SHALL PRE-CHECK ALL SHOP DRAWINGS BEFORE SUBMISSION TO THE ENGINEER FOR REVIEW. ALL SUBMITTAL MATERIALS MUST BEAR AN INITIALED REVIEW STAMP OF THE GENERAL CONTRACTOR. SUBMITTALS WITHOUT THE REVIEW STAMP OF THE GENERAL CONTRACTOR WILL BE RETURNED WITHOUT REVIEW AND SHALL NOT BE CAUSE FOR CLAIMS OF DELAY.
- 6. GENERAL CONTRACTOR SHALL SCHEDULE SUBMITTALS SUFFICIENTLY IN ADVANCE OF THE DATE REQUIRED TO ALLOW REASONABLE TIME FOR DELIVERY, PROCESSING AND REVIEW BY THE DESIGN TEAM. THIS SHALL INCLUDE A MINIMUM OF TEN WORKING DAYS, EXCLUDING DELIVERY TIME, FOR ENGINEER'S PROCESSING AND REVIEW OF SHOP DRAWINGS. INCLUDE TIME FOR CONTRACTOR'S RESUBMISSION AND SUBSEQUENT REVIEW

SHORTER REVIEW PERIODS WILL ONLY BE HONORED WITH PRIOR WRITTEN CONSENT FROM THE ENGINEER. THESE ACCELERATED SERVICES, AND APPROPRIATE COMPENSATION, MUST BE NEGOTIATED WITH THE ENGINEER AND ARCHITECT IN ADVANCE.

FIVE DAY REVIEW PERIODS CAN NOT BE HONORED WHEN LARGE QUANTITIES OF SHOP DRAWINGS ARE SUBMITTED AT ONE TIME. WHEN THIS HAPPENS, THE CONTRACTOR SHALL SUBMIT AN ITEMIZED LIST INDICATING PRIORITIES AND REASONABLE RETURN DATES.

- 7. THE USE OF REPRODUCTIONS OF THESE CONTRACT DRAWINGS, INCLUDING THE USE OF ELECTRONIC FILES, BY ANY CONTRACTOR, SUBCONTRACTOR, ERECTOR, FABRICATOR, OR MATERIAL SUPPLIER IN LIEU OF THE INDEPENDENT PREPARATION OF SHOP DRAWINGS, SIGNIFIES HIS ACCEPTANCE OF ALL INFORMATION SHOWN HEREON AS CORRECT AND OBLIGATES HIMSELF TO ANY JOB EXPENSE, REAL OR IMPLIED, ARISING DUE TO ANY ERRORS THAT MAY OCCUR HEREON. SUCH USE OF REPRODUCTIONS OF THESE CONTRACT DOCUMENTS WILL NOT BE ALLOWED WITHOUT PRIOR CONSENT FROM THE ENGINEER.
- WHEN USING ELECTRONIC FORMAT FOR SUBMITTALS. THE CONTRACTOR SHALL PROVIDE ONE PRINTED HARD COPY FOR ENGINEER REVIEW OR EXECUTE AN AGREEMENT FOR REIMBURSING THE ENGINEER FOR PRINTING COSTS FOR ONE COPY.

#### MODIFICATIONS OF EXISTING STRUCTURE NOTES

- 1. THE CONTRACTOR SHALL INSPECT THE EXISTING STRUCTURE PRIOR TO FABRICATION AND NOTIFY THE ARCHITECT AND ENGINEER OF ANY DISCREPANCIES WITH THE CONTRACT DOCUMENTS OR ANY AREAS ERODED BY RUST, CORROSION, ROT, ETC., WHICH MAY ADVERSELY AFFECT THE RELIABILITY OF NEW CONSTRUCTION
- DIMENSIONS SHOWN FOR, OR TO, THE EXISTING STRUCTURE ARE BASED ON EITHER THE ORIGINAL CONSTRUCTION DOCUMENTS PREPARED FOR THE EXISTING STRUCTURE OR ON APPROXIMATE FIELD MEASUREMENTS. THEY ARE TO BE USED FOR BID PURPOSES ONLY AND NOT FOR SHOP DRAWING PREPARATION OR CONSTRUCTION. ACTUAL CONDITIONS MAY VARY. THE CONTRACTOR SHALL PROVIDE ALL FIELD MEASUREMENTS REQUIRED FOR PROPER FIT UP OF MEMBERS FRAMING TO AND AROUND EXISTING CONSTRUCTION
- 3. THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR THE ADEQUACY OF ALL SHORING (TEMPORARY SUPPORTS) OF THE EXISTING STRUCTURE NECESSARY TO COMPLETE THE CONSTRUCTION AS OUTLINED IN THE STRUCTURAL DRAWINGS. PROVIDE SHORING, BRACES, JACKS, ETC. AS REQUIRED TO COMPLETE THE WORK. ENGINEERING AND DESIGN OF THE TEMPORARY SUPPORTS SHALL BE PERFORMED BY A PROFESSIONAL ENGINEER, ENGAGED BY THE CONTRACTOR, AND REGISTERED IN THE STATE OF THE PROJECT, WITH EXPERIENCE IN THE DESIGN OF THESE ELEMENTS.

#### POST-INSTALLED REBAR AND ANCHORS

THE BELOW PRODUCTS ARE THE DESIGN BASIS FOR THIS PROJECT. PRODUCT DIAMETER AND EMBEDMENT SHALL BE SHOWN IN THE DETAILS. INSTALL PRODUCTS IN ACCORDANCE WITH MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS (MPII). CONTRACTOR SHALL CONTACT MANUFACTURER'S REPRESENTATIVE FOR PRODUCT INSTALLATION TRAINING AND SHALL SUBMIT LETTER TO THE ENGINEER -OF-RECORD (EOR) INDICATING TRAINING HAS TAKEN PLACE. REFER TO THE PROJECT BUILDING CODE AND/OR EVALUATION REPORT FOR SPECIAL INSPECTIONS AND PROOF LOAD REQUIREMENTS. SUBSTITUTION REQUESTS FOR PRODUCTS OTHER THAN THOSE LISTED BELOW MAY BE SUBMITTED BY THE CONTRACTOR TO THE EOR FOR REVIEW. SUBSTITUTIONS WILL ONLY BE CONSIDERED FOR PRODUCTS HAVING A RESEARCH REPORT RECOGNIZING THE PRODUCT FOR THE APPROPRIATE APPLICATION UNDER THE PROJECT BUILDING CODE. SUBSTITUTION REQUESTS SHALL INCLUDE CALCULATIONS THAT DEMONSTRATE THE SUBSTITUTED PRODUCT IS CAPABLE OF ACHIEVING THE EQUIVALENT PERFORMANCE VALUES OF THE DESIGN BASIS PRODUCT.

#### UNLESS OTHERWISE NOTED ON THE PLANS, ANCHORS SHALL BE:

#### FOR ANCHORING INTO CONCRETE:

- A. MECHANICAL ANCHORS SHALL HAVE BEEN TESTED IN ACCORDANCE WITH ACI 355.2 AND ICC-ES AC193 FOR CRACKED CONCRETE. PRE-APPROVED PRODUCTS INCLUDE:
  - I. SIMPSON STRONG-TIE "STRONG-BOLT 2" (ICC-ES ESR-3037)
  - II. SIMPSON STRONG-TIE "TITEN-HD" (ICC-ES ESR-2713)
  - III. SIMPSON STRONG-TIE "STAINLESS STEEL TITEN HD" (IAPMO-UES ER-493)
  - IV. HILTI "KWIK BOLT TZ" (ICC-ES ESR-1917)
  - V. DEWALT SCREW BOLT + (ICC-ES ESR-3889) VI. DEWALT POWER-STUD + SD1 (ICC-ES ESR-2818)
- B. ADHESIVE FOR REBAR AND ANCHORS SHALL HAVE BEEN TESTED IN ACCORDANCE WITH ACI 355.4 AND ICC-ES AC308 FOR CRACKED CONCRETE APPLICATIONS. DESIGN ADHESIVE BOND STRENGTH HAS BEEN BASED ON ACI 355.4 TEMPERATURE RANGE A WITH INSTALLATIONS INTO DRY HOLES DRILLED USING CARBIDE DRILL BIT INTO CRACKED CONCRETE THAT HAS CURED FOR AT LEAST 21 DAYS. ADHESIVE ANCHORS REQUIRING CERTIFIED INSTALLATIONS SHALL BE INSTALLED BY A CERTIFIED ADHESIVE ANCHOR INSTALLER PER ACI 318-14 17.8.2.2. INSTALLATIONS REQUIRING CERTIFIED INSTALLERS SHALL BE INSPECTED PER ACI 318-14 17.8.2.4. PRE-APPROVED PRODUCTS
- SIMPSON STRONG-TIE "AT-XP" W/ SPEED CLEAN DXS DUST EXTRACTION SYSTEM (IAPMO-UES ER-263)
- II. SIMPSON STRONG-TIE "SET-XP" W/ SPEED CLEAN DXS DUST EXTRACTION SYSTEM (ICC-ES ESR-2508) III. SIMPSON STRONG-TIE "SET-3G" (ICC-ES ESR-4057)
- IV. HILTI "HIT-HY 200 SAFE SET SYSTEM w/ HILTI HIT-Z ROD" (ICC-ES ESR-3187)
- V. HILTI "HIT-HY 200 SAFE SET SYSTEM w/ HILTI HOLLOW DRILL BIT SYSTEM" (ICC-ES ESR-3187)
- VI. HILTI "HIT-RE 500 V3" (ICC-ES ESR-3814) VII. DEWALT PURE 110+ EPOXY SYSTEM (ICC-ES ESR-3298)
- VIII. DEWALT PURE 110+ EPOXY SYSTEM (ICC-ES ESR-3298) W/ DEWALT HOLLOW DUST X SYSTEM IX. DEWALT AC200+ ACRYLIC ADHESIVE SYSTEM (ICC-ES ESR-4027)
- X. DEWALT AC200+ ACRYLIC ADHESIVE SYSTEM (ICC-ES ESR-4027) W/ DEWALT HOLLOW DUST X

#### FOR ANCHORING INTO MASONRY:

#### A. SOLID-GROUTED CONCRETE MASONRY

- MECHANICAL ANCHORS SHALL HAVE BEEN TESTED IN ACCORDANCE WITH ICC-ES AC01 OR ICC-ES AC106. PRE-APPROVED PRODUCTS INCLUDE:
- (1) SIMPSON STRONG-TIE "TITEN-HD" (ICC-ES ESR-1056)
- (2) SIMPSON STRONG-TIE "STRONG-BOLT 2" (IAPMO-UES ER-240)

(5) DEWALT SCREW-BOLT+ (ICC-ES ESR-4042)

- (3) HILTI "KWIK BOLT 3" (ICC-ES ESR-1385) (4) DEWALT POWER-STUD + SD1 (ICC-ES ESR-2966)
- II. ADHESIVE FOR REBAR AND ANCHORS SHALL HAVE BEEN TESTED IN
- (1) SIMPSON STRONG-TIE "AT-XP" (IAPMO-UES ER-281) (2) SIMPSON STRONG-TIE "SET-XP" (IAPMO-UES ER-265)
- (3) HILTI HIT-HY 70 MASONRY ADHESIVE ANCHORING SYSTEM (ICC-ES ESR 2682) (4) DEWALT AC100+GOLD (ICC-ES ESR-3200)

ACCORDANCE WITH ICC-ES AC58. PRE-APPROVED PRODUCTS INCLUDE:

# B. HOLLOW CONCRETE MASONRY

- I. MECHANICAL ANCHORS SHALL HAVE BEEN TESTED IN ACCORDANCE WITH ICC-ES AC106. PRE-APPROVED PRODUCTS INCLUDE:
  - (1) SIMPSON STRONG-TIE "TITEN-HD" (ICC-ES ESR-1056)
- II. ADHESIVE FOR REBAR AND ANCHORS SHALL HAVE BEEN TESTED IN ACCORDANCE WITH ICC-ES AC58. THE APPROPRIATE SCREEN TUBE SHALL BE USED AS RECOMMENDED BY THE ADHESIVE MANUFACTURER. PRE-APPROVED PRODUCTS INCLUDE:
- (1) SIMPSON STRONG-TIE "SET-XP" (IAPMO-UES ER-265)
- (2) HILTI HIT-HY 70 MASONRY ADHESIVE ANCHORING SYSTEM (ICC-ES ESR-2682)

(3) DEWALT AC100+GOLD (ICC-ES ESR-3200)

Jose I. Guerra, Inc. Consulting Engineers 2401 South IH-35 Suite 210 Austin, Texas 78741 (512) 445-2090Structural ◆ Civil ◆ Mechanical ◆ Electrical TBPE FIRM F-3





305 East Huntland Drive Suite 200 Austin, Texas 78752 p: 512.453.0767 f: 512.453.1734 TBPE FIRM REGISTRATION NO.: F-1416 FIRM REGISTRATION NO.: 1006560

NO.

DATE DESCRIPTION BY The bar above measures one inch on the original drawing. Adjust scales accordingly

**GENERAL NOTES** 

PLOTTED: 11/27/2020 JOB NO: 023-92B

KGSC TRUCK WASH FACILITY PROPOSED IMPROVEMENTS 4108 TODD LANE **AUSTIN, TEXAS 78744** 

# STATEMENT OF SPECIAL INSPECTION PER IBC 2015, CHAPTER 17 PER 2015 INTERNATIONAL BUILDING CODE, THE FOLLOWING IS A LIST OF THE REQUIRED SPECIAL INSPECTIONS APPLICABLE FOR THIS PROJECT:


2015 IBC SECTION	TYPE OF SPECIAL INSPECTIONS AND EXTENT	APPLICABLE	NON APPLICABLE	NON STRUCTURAL
1705.2	STEEL CONSTRUCTION			
1705.2.2	COLD-FORMED WELDING INSPECTION			
1705.2.4	COLD-FORMED STEEL TRUSSES SPANNING 60 FEET OR GREATER			
1705.3	CONCRETE CONSTRUCTION			
1705.3.1	REINFORCING STEEL WELDING INSPECTION			
1705.4	MASONRY CONSTRUCTION			
1705.5	WOOD CONSTRUCTION			
1705.6	SOILS			
1705.7	DRIVEN DEEP FOUNDATIONS			
1705.8	CAST-IN-PLACE DEEP FOUNDATIONS (PIERS)			
1705.9	HELICAL PILE FOUNDATIONS			
1705.11	SPECIAL INSPECTION FOR WIND RESISTANCE			
1705.12	SPECIAL INSPECTION FOR SEISMIC RESISTANCE			
1705.13	TESTING FOR SEISMIC RESISTANCE			
1705.14	SPRAYED FIRE-RESISTANCE MATERIALS			
1705.15	MASTIC AND INTUMESCENT FIRE-RESISTANT COATINGS			
1705.16	EXTERIOR INSULATION AND FINISH SYSTEMS/ WATER-RESISTIVE BARRIER COATING			
1705.17	FIRE-RESISTANCE PENETRATIONS AND JOINTS			
1705.18	SPECIAL INSPECTION FOR SMOKE CONTROL			
1706	DESIGN STRENGTH OF MATERIALS			
1707	ALTERNATIVE TEST PROCEDURES			
1708	IN-SITU LOAD TESTS			
1709	PRECONSTRUCTION LOAD TESTS			

# **ABBREVIATIONS**

AB	ANCHOR BOLT	FD	FLOOR DRAIN	PSF	POUNDS PER SQUARE FOOT
ADDL	ADDITIONAL	FDN	FOUNDATION	PROJ	PROJECTION
ADH	ADHESIVE	FIN	FINISH	P/S	PUMP STATION
AFF	ABOVE FINISH FLOOR	FLG	FLANGE	PVC	POLYVINYL CHLORIDE
AL	ALUMINUM	FLR	FLOOR	RD	ROOF DRAIN
ALT	ALTERNATE	FO	FACE OF	REINF	REINFORCEMENT, REINFORCING
ANC	ANCHOR	FRMG	FRAMING	REQD	REQUIRED
APVD	APPROVED	FRP	FIBER REINFORCED POLYMER	RTN	RETURN
ARCH	ARCHITECT, ARCHITECTURAL	FS	FAR SIDE	SBD	SCHEDULED BEAM DEPTH
ВС	BOTTOM CHORD	FT	FOOT / FEET	SCHED	SCHEDULE / SCHEDULED
BLDG	BUILDING	FTG	FOOTING	SHT	SHEET
BM	BEAM	GA	GAUGE, GAGE	SIM	SIMILAR
BOC	BOTTOM OF CONCRETE	GALV	GALVANIZED	SLV	SHORT LEG VERTICAL
BOS	BOTTOM OF STEEL	GB	GRADE BEAM	SOG	SLAB ON GRADE
ВОТ	ВОТТОМ	GRD	GRADE	SPA	SPACING
BRG	BEARING	GRT	GROUT	SPCS	SPACES
BTWN	BETWEEN	GRTG	GRATING	SPECS	SPECIFICATIONS
CC	CENTER TO CENTER	Н	HIGH	SQ	SQUARE
CFM	COLD FORMED METAL	HCA	HEADED CONCRETE ANCHOR	SS	STAINLESS STEEL
CHKD	CHECKERED / CHECKED	HD	HOT DIPPED	SSH	SHORT SLOTTED HOLE
CIP	CAST IN PLACE	HORIZ	HORIZONTAL	STD	STANDARD
CJ	CONSTRUCTION JOINT	HSB	HIGH STRENGTH BOLT	STIFF	STIFFENER
CL, G	CENTERLINE	IF	INSIDE FACE	STIR	STIRRUP
CLR	CLEARANCE / CLEAR	ii IN	INCH(ES)	STL	STEEL
CMU	CONCRETE MASONRY UNIT	JT	JOINT	SYM	SYMMETRICAL
COL(S)	COLUMN(S)	L	LOW	T&B	TOP & BOTTOM
CONC	CONCRETE	LONG	LONGITUDINAL	T/	TOP OF
CONN	CONNECTION	LLH	LONG LEG HORIZONTAL	T/PL	TOP OF PLATE
CONT	CONTINUOUS	LLV	LONG LEG VERTICAL	T/SL	TOP OF SLAB
CTR	CENTER	LSH	LONG SLOTTED HOLE	TC	TOP CHORD
CTRD	CENTERED	MAINT	MAINTENANCE	TD	TRUSS DIAGONAL
DBA	DEFORMED BAR ANCHOR	MAX	MAXIMUM	TEMP	TEMPORARY/TEMPERATURE
DEMO	DEMOLITION			THK	THICK
		MB	MACHINE BOLT		TOP OF
DIA, Ø	DIAMETER	MEP	MECHANICAL, ELECTRICAL, & PLUMBING	TO.	
DIM	DIMENSION	MECH	MECHANICAL	TOC	TOP OF CONCRETE
DIST	DISTANCE	MFR	MANUFACTURER	TOF	TOP OF FOOTING
DN	DOWN	MIN	MINIMUM	TOG	TOP OF GRATING
DP	DEEP	MTL	METAL	TOS	TOP OF SLAB / STEEL
DS	DRILLED SHAFT	NOM	NOMINAL	TOW	TOP OF WALL
DWG	DRAWING	NS	NEAR SIDE	TRANS	TRANSVERSE
EA	EACH	NTS	NOT TO SCALE	TV	TRUSS VERTICAL
ECS	EPOXY COATED STEEL	OC	ON CENTER	TYP	TYPICAL
EE	EACH END	OD	OUTSIDE DIAMETER	UNO	UNLESS NOTED OTHERWISE
EF	EACH FACE	OF	OUTSIDE FACE	UT	ULTRASONIC TESTING
EJ	EXPANSION JOINT	O/O	OUT TO OUT	VERT	VERTICAL
EL, ELEV	ELEVATION / ELEVATOR	OPNG	OPENING	VIF	VERIFY IN FIELD
EOR	ENGINEER OF RECORD	OPP	OPPOSITE	W	WIDE
EQ	EQUAL	OSH	OVERSIZED HOLE	W/ w/	WITH
EQUIP	EQUIPMENT	PC	PRECAST	WP	WORK POINT
EQUIV	EQUIVALENT	PEMB	PRE-ENGINEERED METAL BUILDING	WS	WATERSTOP
ES	EACH SIDE	PGL	PROFILE GRADE LINE	WWF	WELDED WIRE FABRIC
EW	EACH WAY	PJF	PREMOLDED JOINT FILLER		
EXP	EXPANSION	PL, P	PLATE		
EXIST	EXISTING	PLF	POUNDS PER LINEAR FOOT		


Jose I. Guerra, Inc.
Consulting Engineers

2401 South IH-35 Suite 210
Austin, Texas 78741
(512) 445-2090
Structural • Civil • Mechanical • Electrical
TBPE FIRM F-3






	NO.	DATE	DESCRIPTION	BY	
L					
					l n
ŀ					"
ŀ					
00					S
١					



# SPECIAL INSPECTION AND ABBREVIATIONS

PLOTTED: 11/27/2020 JOB NO: 023-92B

S-2





1 NEW TRENCH AND SUMP PIT PLAN IN EXISTING FOUNDATION

SCALE: 1/4" = 1'-0"



NOTE :
1. REFER TO ARCH DRAWINGS FOR TOP OF SLAB ELEVATIONS





		NONO.	l M
mwm Design	Group	305 East Huntland Drive Suite 200 Austin, Texas 78752 p: 512.453.0767 f: 512.453.1734	
	TBPE FIRM RE	GISTRATION NO.: 1452 GISTRATION NO.: F-1416 EGISTRATION NO.: 10065600	


DESCRIPTION	BY	
90% DESIGN DOCUMENTS 11/13/2020		The bar above measures one inch on the original drawing. Adjust
		scales accordingly.


NEW TRENCH AND SUMP PIT PLAN
IN EXISTING FOUNDATION


PLOTTED: 11/27/2020 JOB NO: 023-92B


KGSC TRUCK WASH FACILITY PROPOSED IMPROVEMENTS
4108 TODD LANE
AUSTIN, TEXAS 78744

S-3










Jose I. Guerra, Inc.
Consulting Engineers

2401 South IH-35 Suite 210
Austin, Texas 78741
(512) 445-2090
Structural • Civil • Mechanical • Electrical
TBPE FIRM F-3





# CONCRETE DETAILS

PLOTTED: 11/27/2020 JOB NO: 023-92B

KGSC TRUCK WASH FACILITY PROPOSED IMPROVEMENTS
4108 TODD LANE
AUSTIN, TEXAS 78744

S-4